



CLARIFICATION 1

އަލާމަތްތަކުގެ ބަޔާން 1


ނަންބަރު No:	TES/2019/W-031	
ފޮތް ނަންބަރު Project:	Construction of Toilet Block at Central Park Area	
ދުވަހުގެ Issued Date	7 th March 2019	
ސަފުހާގެ އަދަދު No. of Pages: -03	ބޮޑުވަނަ Boq: -00	ވަނަވަނަ Drawings: -00

Please include this amendment when submitting the bid. ބަޔާންތަކުގެ ބަޔާން ހިމަނާ ފަދަ ގޮތުގައި ދަނީ ހުށަހަޅާން ޖެހޭނެ ގޮތުގައި ބަޔާންކުރެއްވުމަށް ދަންނަވަމެވެ.

- Find attached clarification 1.

ނަންބަރު
Name: Fathimath Rishfa Ahmed

ސަފްޞަފާ
Signature:



Clarifications for Central park toilet block project

1. What's the distance from the nearest Distribution Box to the building?
 - The distance to be measured is to be given in BOQ in meters
2. Ground water could be used to any kind of construction works?
 - Ground water cannot be used for any kind of construction works.
3. Is there any site visit for this project?
 - Interested parties can visit the site at any time.

PRELIMINARIES:

1. Power & Water provision (Distance where you could get the connections for the building)?
 - The distance to be measured is to be given in BOQ in meters
2. Barricading material like plywood or screen mesh cloth, and height of barricading?
 - Barricading material and height should be according to health and safety regulation.

CIVIL:

1. Please provide the difference in level of existing ground level and natural ground level?
 - There is no difference in ground levels
2. Planter box thickness
 - Thickness is 100mm
3. Please Testing for concrete only or anything else?
 - Testing is required for concrete only
4. Alternative to clay brick, since it is not available in Maldives
 - Clay bricks should be used as it is specified by the designer.



5. Brick dimension not clear
 - Brick dimension is 75 x 75 x 200mm
6. Gauge or thickness of corrugated GI sheets
 - 0.5 mm
7. Polycarbonate roof sheet thickness and color.
 - Depends on the market availability. At least 15mm thick.
8. Optional brands of paint.
 - The optional brand of paint is Nippon or equivalent. (To be approved by the ministry)
9. is it required to polish the screed floor?
 - It is required to polish the screed floor.
10. Any specific optional brands of MEP, Tiles & paint products, so that BOQ shall be prepared based on this.
 - All mechanical and plumbing items should be locally available to replace or service. No specific brand or manufacturer for tiles

BIDDING DOCUMENT

1. Defect liability period 365 days or 365 months?
 - It is 365 days.

