

Project name: D & B R.Rasgetheemu Harbour

Project number: TES/2019/W-131

CLARIFICATION REQUEST / QUESTIONS TO THE CLIENT

ID	MTH - QUESTIONS TO CLIENT	CLIENT / ENGINEER'S RESPONSE
	<b>Harbour works</b>	
1	Please specify the location for dispose the dredging material and the demolish debrees within the Island.	<b>Location for dispose will be identified during EIA stage and after the scoping and community consultation.</b>
2	Do we need to backfill existing entrance channel area?	<b>Yes</b>
3	Please specify the Ramp location ?	<b>Ramp location will be decided during design stage</b>
4	Please specify details of the floating platform as mentioned in the no.12 of Employer's Requiremnts in Section IV. Also there was no BOQ item. Pleae clarify	<b>You are to propose the items in the BOQ and Drawing only</b>
5	As per No.13 Concrete Walkway required to access the long break water, but it is not specyfied in the concept drawings and BOQ? Please advise and provide details	<b>You are to propose the items in the BOQ and Drawing only</b>
6	Does the project require the use of a Government registered Permanent Station Mark?	<b>Yes</b>
	<b>Jetty works</b>	
7	Please specify Required maximum design load for jetty	<b>Should cater for 1.5tonn vehicle</b>
8	Please specify type and size of fenders for jetty	<b>Use D type Fenders, you are to propose adequate number and size of fenders.</b>
9	Do we need to include Feeder Power cable for lights? Please specify the location of panel board/Feeder Point?	<b>Yes, Feeder Power Cable should be included. It should be connected to the nearest distibution box in the island.</b>
	<b>Pre Qualification Documents</b>	
10	Form CON -1 mentioned in Item 2.2 Litigation History under section III -Evaluation and Qualification Criteria, but it is not avilable under Section IV -Tendering Forms. Please provide.	<b>Form CON -1 is not applicable for this project.</b>