كب الندازمن إزحيهم



## **Ministry of Finance**

Ameenee Magu, Male', Republic of Maldives Telephone: (960) 334 9266, Fax: (960) 332 0706 ورس في براد وسر ماد و مرد المرد في المرد المرد

## **CLARIFICATION 1**

لأؤبرولا شوشرا

سَرُسْرُهُ مَر No:	TES/2020/W-002	
Project:	Construction of Fish Market at Villimale'	
Issued Date	11 <sup>th</sup> February 2020	
ار دُورَ مُرَوَّدُ اللهِ ا No. of Pages: -01	34.3.9 Boq: -00	تورورو Drawings: -00

والمُ المُرَكْدُوُ مِنْ وَ وَ مِنْ وَالْمُ اللَّهِ مِنْ مِنْ وَمُرَكُونُونُ فَي مِنْ مُرْكُونُونُ فَي وَعَلَي وَسُرَو اللَّهِ اللَّهِ اللَّهِ اللَّهِ اللَّهُ اللّ

## > Below please find the clarifications for the queries

1. Please inform advance payment.

Please refer to Addendum 3

2. Please inform Performance security %

Please refer to Addendum 3

3. Please inform intended duration for this project.

Duration shall be proposed by the contractor

4. Please clarify the availability of material storage within the site premises.

There is no such Material storage within the area

- 5. Please confirm the source of temporary electricity and Water connection nearby site area.

  There is a source for temporary Electricity but no water connection nearby the site area
- 6. Please provide the site condition and demolition of any building or trees need to cut or transported.

There are 3 Pine trees (fithuroanu) and 01 Dhiggaa Gas within the site area to be cut and demolish by the contractor (no buildings)

- 7. Please confirm whether manufactured rock sand can be used for structural concrete work.

  Manufactured rock sand can be used
- 8. Please confirm whether blocks/bricks casted by local sand can be used for masonry works. River sand should be used

9. Electrical Connection is given in the BOQ, kindly provide the distance from the electrical Main DB.

The distance from the electrical main DB to the area is 210 Sqft

Name: Fathimath Rishfa Ahmed

مرير

Signature:

