ARCHITECTURAL & STRUCTURAL DRAWINGS OF

PROPOSED 02 STOREY BUILDING

R. ATOLL EDUCATION CENTRE

2 STOREY BUILDING

Ministry Of Education

TABLE OF CONTENTS

DRAWING No.	TITLE	REVISION No.	DATE	REMARKS
A R C H I T E C T U R A L		---	---	---
A - 01 /16	SITE PLAN	---	---	---
A - 02 /16	GROUND FLOOR PLAN	---	---	---
A - 03 /16	FIRST FLOOR PLAN	---	---	---
A - 04 /16	ROOF PLAN	---	---	---
A - 05 /16	SECTION X-X, SECTION Y-Y	---	---	---
A - 06 /16	ELEVATION E1, ELEVATION E2	---	---	---
A - 07 /16	ELEVATION E3, ELEVATION E4	---	---	---
A - 08 /16	GROUND FLOOR FLOOR FINISHES PLAN	---	---	---
A - 09 /16	FIRST FLOOR FLOOR FINISHES PLAN	---	---	---
A - 10 /16	GROUND FLOOR REFLECTED CEILING PLAN	---	---	---
A - 11 /16	FIRST FLOOR REFLECTED CEILING PLAN	---	---	---
A - 12 /16	DOOR & WINDOW SCHEDULE - 1	---	---	---
A - 13 /16	DOOR & WINDOW SCHEDULE - 2	---	---	---
A - 14 /16	DOOR & WINDOW SCHEDULE - 3	---	---	---
A - 15 /16	DOOR & WINDOW SCHEDULE - 4	---	---	---
A - 16 /16	VENTILATION SCHEDULE	---	---	---
		---	---	---
		---	---	---
		---	---	---
		---	---	---
		---	---	---
		---	---	---
S T R U C T U R A L		---	---	---
E - 00 /18	GENERAL NOTES	---	---	---
E - 01 /18	FOUNDATION PLAN	---	---	---
E - 02 /18	COLUMN LAYOUT PLAN	---	---	---
E - 03 /18	FIRST FLOOR BEAM PLAN	---	---	---
E - 04 /18	FIRST FLOOR SLAB REINFORCEMENT PLAN	---	---	---
E - 05 /18	ROOF BEAM LEVEL 1	---	---	---
E - 06 /18	ROOF BEAM LEVEL 2	---	---	---
E - 07 /18	ROOF TRUSS	---	---	---
E - 08 /18	ROOF FRAMING PLAN	---	---	---
E - 09 /18	STRUCTURAL DETAILS	---	---	---
E - 10 /18	TYPICAL WALL CONSTRUCTION DETAIL	---	---	---
E - 11 /18	WALL CONSTRUCTION DETAIL	---	---	---
E - 12 /18	RAILING DETAIL	---	---	---
E - 13 /18	RC WALL DETAIL			
E - 14 /18	MAIN ENTRANCE RAMP DETAIL	---	---	---
E - 15 /18	STAIR DETAILS	---	---	---
E - 16 /18	TRUSS DETAIL	---	---	---
E - 17 /18	TOILET DETAILS (MALE & FEMALE)	---	---	---
E - 18 /18	DISABLE TOILET DETAILS	---	---	---



SITE PLAN

NTS

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-01/ 15



GROUND FLOOR PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

NOTE:

- PROPOSED 150mm THICK SOLID BLOCK - INTERIOR MASONRY WALL WITH 16mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH
- PROPOSED 150mm THICK SOLID BLOCK - EXTERIOR MASONRY WALL WITH 20mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH
- PROPOSED 100mm THICK SOLID BLOCK - INTERIOR MASONRY WALL WITH 16mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH
- PROPOSED 120mm THICK RC WALL TO BE WATER PROOFED WITH WATER PROOFING AGENT
- PROPOSED 100mm THICK 2400mm HIGH SOLID BLOCK MASONRY WALL WITH 16mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH

THE SCREEDING AND TILES ARE INCORPORATED IN THE FLOOR FINISH LEVELS

REFER TO ARCHITECT FOR FURTHER ASSISTANCE.

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-02/ 15



GROUND FLOOR PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

NOTE:

- PROPOSED 150mm THICK SOLID BLOCK - INTERIOR MASONRY WALL WITH 16mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH
- PROPOSED 150mm THICK SOLID BLOCK - EXTERIOR MASONRY WALL WITH 20mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH
- PROPOSED 100mm THICK SOLID BLOCK - INTERIOR MASONRY WALL WITH 16mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH
- PROPOSED 120mm THICK RC WALL TO BE WATER PROOFED WITH WATER PROOFING AGENT
- PROPOSED 100mm THICK 2400mm HIGH SOLID BLOCK MASONRY WALL WITH 16mm PLASTERING, GROUND SMOOTH IN SELECTED PAINT FINISH

THE SCREEDING AND TILES ARE INCORPORATED IN THE FLOOR FINISH LEVELS

REFER TO ARCHITECT FOR FURTHER ASSISTANCE.

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-02/ 15



ROOF PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-04/ 15



SECTION XX

SCALE 1:100

0 0.5 1 2 3 4 5



SECTION YY

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-05/ 15



ELEVATION E1

SCALE 1:100

0 0.5 1 2 3 4 5

ELEVATION E2

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : A-06/ 15



ELEVATION E3

SCALE 1:100

0 0.5 1 2 3 4 5

ELEVATION E4

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT

R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-07/ 15



GROUND FLOOR FLOOR FINISHES PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

LEGEND

CODE	DESCRIPTION
	600X600mm HOMOGENOUS NON-SLIP TILES OVER 50mm SCREEDING
	35mm NORMAL SCREEDING WITH 2.5mm SELF LEVELING CEMENT WITH EPOXY FLOOR PAINT (2 COATS EPOXY)
	300X300mm HOMOGENOUS NON-SLIP TILES OVER 25mm SCREEDING
	600X600mm HOMOGENOUS NON-SLIP TILES OVER 25mm SCREEDING (CEMENTITIOUS WATERPROOFING: MASTERPEL 588 OR EQUIVALENT ON TOP OF THE SLAB)

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-08/ 15



FIRST FLOOR FLOOR FINISHES PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

LEGEND

CODE	DESCRIPTION
	600X600mm HOMOGENOUS NON-SLIP TILES OVER 50mm SCREEDING
	35mm NORMAL SCREEDING WITH 2.5mm SELF LEVELING CEMENT WITH EPOXY FLOOR PAINT (2 COATS EPOXY)
	300X300mm HOMOGENOUS NON-SLIP TILES OVER 25mm SCREEDING
	600X600mm HOMOGENOUS NON-SLIP TILES OVER 25mm SCREEDING (CEMENTITIOUS WATERPROOFING: MASTERPEL 588 OR EQUIVALENT ON TOP OF THE SLAB)

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-09/ 15



GROUND FLOOR REFLECTED CEILING PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

LEGEND

CODE	DESCRIPTION
	EXPOSED SLAB SOFFIT TO BE GROUND SMOOTH IN SELECT PAINT FINISH (ONE COAT OF PUTTY FOLLOWED BY SEALER AND 2 COATS OF PAINT)
	6mm THICK CEMENT BOARD ON ROOF EAVE/GABLE CEILING (ONE COAT OF PUTTY FOLLOWED BY SEALER AND 2 COATS OF PAINT)

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-10/ 15



FIRST FLOOR REFLECTED CEILING PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

LEGEND

CODE	DESCRIPTION
	9mm THICK FIXED CEILING 'BORAL' OR EQUIVALENT PLASTERBOARD CEILING SYSTEM WITH TIMBER FRAMES, APPLIED WITH GROUND SMOOTH FINISH IN SELECTED PAINT
	6mm THICK CEMENT BOARD ON ROOF EAVE/GABLE CEILING (ONE COAT OF PUTTY FOLLOWED BY SEALER AND 2 COATS OF PAINT)

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A-11/ 15

2D Symbol



B.T.L

B.B.L



F.F.L

D1	SWING DOOR
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINIUM PANEL OF SELECTED COLOUR
LOCATION	TOILET STALLS
QUANTITY	08 NOS
OPEN AREA	1.39 sqm

2D Symbol



B.T.L

B.B.L



F.F.L

D2	SWING DOOR
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINIUM PANEL OF SELECTED COLOUR
LOCATION	STORE & CLEANER CLOSET
QUANTITY	04 NOS
OPEN AREA	1.72sqm

2D Symbol



B.T.L

B.B.L



F.F.L

D3	SWING DOOR
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINIUM PANEL OF SELECTED COLOUR
LOCATION	TOILET
QUANTITY	04 NOS
OPEN AREA	1.39 sqm

NOTE:-
- ALL DOORS & WINDOWS TO BE CHECKED ON SITE BEFORE FABRICATION.
- ALL DOOR & WINDOWS VIEWED FROM EXTERIOR, FOR DOOR SWING, REFER TO FLOOR PLANS.
- THE DOORS / WINDOWS WHICH DO NOT TOUCH THE BEAM SHALL HAVE A LINTEL BEAM (LB) ABOVE THE DOOR / WINDOW.
- FOR ALL THE WINDOWS PUT A SILL BEAM BELOW THE WINDOW (SB)
- FOR SAFETY PURPOSES REFER TO TECHNICAL SPECIFICATIONS FOR GLASS THICKNESS.
  - ALUMINIUM FRAME PROFILE SHALL BE 35-50MMX100MM (MIN 1,6MM THICK)
  - ALUMINIUM PANELS SHOULD BE MINIMUM 6MM THICK SINGLE SHEET WITHIN AN ALUMINIUM PROFILE OF 35-50MM X 100MM (MIN 1.6MM THICK)
  - TIMBER DOOR FRAME SHALL BE 50MMX100MM HARDWOD
  - ALL DOOR PANEL THICKNESS SHOULD BE 40MM THICK SOLID CORE
  - ALL FRAMES EDGED SHALL BE TRIMMED 3MM
  - ALL WOODEDN COMPONENTS SHOULD BE WOOD STAINED FINISH
  - ALL GLAZING SHOULD BE OF 6MM UNLESS SPECIFIED
  - EXTERNAL UNITS MUST COMPLY THE FOLLOWING WEATHER CONDITIONS :
    WIND PRESSURE :200KG/SQM
    WATER TIGHTNESS : 25KG/SQM
  - ALL EXTERNAL FRAMES / WALL JOINTS MS BE SEALED WITH SILICON SEALANT AND THE EDGES TRIMMED WITH 12X12MM HARDWOOD BEADING FIXED TO FRAMED BY NAILS
  - ALL HARDWARE SHOULD BE PROVIDED FOR THE PERFORMANCE OF ALL FUNCTIONS OF THE UNITS
  - HINGES SHALL CONFIRM TO :
    1. DOOR SIZE MORE THAN 700X900MM
       WD : 125MM X 2SETS
       SD: 150MM X 3SETS
    2. DOOR SIZE LESS THAN 700X1900MM
       WD : 100MM X 2SETS
       SD: 125MM X 2SETS
  - LOCKS SHALL BE CYLINDRICAL WITH MASTER KEY SETS
  - DOOR KNOBS SHALL BE 1000MM ABOVE FFL

LEGEND:
CG - CLEAR GLASS
RG - REFLECTED GLASS
AL - ALUMINIUM
PVC - POLYVINYL CHLORIDE

DOOR & WINDOW SCHEDULE - 1

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A 9 / 19

2D Symbol



D4	SWING DOOR
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINIUM PANEL OF SELECTED COLOUR
LOCATION	DISABLED TOILET
QUANTITY	01 NOS
OPEN AREA	1.39 sqm

2D Symbol



D5	SWING DOOR
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINIUM PANEL AND 6mm THICK CLEAR GLASS
LOCATION	CLASSROOM
QUANTITY	12 NOS
OPEN AREA	1.39 sqm

2D Symbol



W1	SLIDING WINDOW
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINIUM PANEL AND 6mm THICK CLEAR GLASS
LOCATION	CLASSROOMS
QUANTITY	12 NOS
OPEN AREA	0.92 sqm

NOTE:-
- ALL DOORS & WINDOWS TO BE CHECKED ON SITE BEFORE FABRICATION.
- ALL DOOR & WINDOWS VIEWED FROM EXTERIOR, FOR DOOR SWING, REFER TO FLOOR PLANS.
- THE DOORS / WINDOWS WHICH DO NOT TOUCH THE BEAM SHALL HAVE A LINTEL BEAM (LB) ABOVE THE DOOR / WINDOW.
- FOR ALL THE WINDOWS PUT A SILL BEAM BELOW THE WINDOW (SB)
- FOR SAFETY PURPOSES REFER TO TECHNICAL SPECIFICATIONS FOR GLASS THICKNESS.
  - ALUMINIUM FRAME PROFILE SHALL BE 35-50MMX100MM (MIN 1,6MM THICK)
  - ALUMINIUM PANELS SHOULD BE MINIMUM 6MM THICK SINGLE SHEET WITHIN AN ALUMINIUM PROFILE OF 35-50MM X 100MM (MIN 1.6MM THICK)
  - TIMBER DOOR FRAME SHALL BE 50MMX100MM HARDWOD
  - ALL DOOR PANEL THICKNESS SHOULD BE 40MM THICK SOLID CORE
  - ALL FRAMES EDGED SHALL BE TRIMMED 3MM
  - ALL WOODEDN COMPONENTS SHOULD BE WOOD STAINED FINISH
  - ALL GLAZING SHOULD BE OF 6MM UNLESS SPECIFIED
  - EXTERNAL UNITS MUST COMPLY THE FOLLOWING WEATHER CONDITIONS :
    WIND PRESSURE :200KG/SQM
    WATER TIGHTNESS : 25KG/SQM
  - ALL EXTERNAL FRAMES / WALL JOINTS MS BE SEALED WITH SILICON SEALANT AND THE EDGES TRIMMED WITH 12X12MM HARDWOOD BEADING FIXED TO FRAMED BY NAILS
  - ALL HARDWARE SHOULD BE PROVIDED FOR THE PERFORMANCE OF ALL FUNCTIONS OF THE UNITS
  - HINGES SHALL CONFIRM TO :
    1. DOOR SIZE MORE THAN 700X900MM
       WD : 125MM X 2SETS
       SD: 150MM X 3SETS
    2. DOOR SIZE LESS THAN 700X1900MM
       WD : 100MM X 2SETS
       SD: 125MM X 2SETS
  - LOCKS SHALL BE CYLINDRICAL WITH MASTER KEY SETS
  - DOOR KNOBS SHALL BE 1000MM ABOVE FFL

LEGEND:
CG - CLEAR GLASS
RG - REFLECTED GLASS
AL - ALUMINIUM
PVC - POLYVINYL CHLORIDE

DOOR & WINDOW SCHEDULE - 2

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A 10/ 19

2D Symbol



W2	SWING WINDOW
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WINDOW WITH 6mm THICK REFLECTIVE GLASS
LOCATION	CLASSROOMS , CLEANER CLOSET
QUANTITY	09 NOS
OPEN AREA	4.24 sqm

2D Symbol



V1	WINDOW WITH ALUMINUM LOUVERS
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINUM LOUVERS
LOCATION	TOILETS & MAIN SWITCH BOARD STORE
QUANTITY	04 NOS
OPEN AREA	0.36 SQM

2D Symbol



V2	WINDOW WITH ALUMINUM LOUVERS
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINUM LOUVERS
LOCATION	TOILETS & MAIN SWITCH BOARD STORE
QUANTITY	04 NOS
OPEN AREA	1.87 SQM

NOTE:-
- ALL DOORS & WINDOWS TO BE CHECKED ON SITE BEFORE FABRICATION.
- ALL DOOR & WINDOWS VIEWED FROM EXTERIOR, FOR DOOR SWING, REFER TO FLOOR PLANS.
- THE DOORS / WINDOWS WHICH DO NOT TOUCH THE BEAM SHALL HAVE A LINTEL BEAM (LB) ABOVE THE DOOR / WINDOW.
- FOR ALL THE WINDOWS PUT A SILL BEAM BELOW THE WINDOW (SB)
- FOR SAFETY PURPOSES REFER TO TECHNICAL SPECIFICATIONS FOR GLASS THICKNESS.
  - ALUMINIUM FRAME PROFILE SHALL BE 35-50MMX100MM (MIN 1,6MM THICK)
  - ALUMINIUM PANELS SHOULD BE MINIMUM 6MM THICK SINGLE SHEET WITHIN AN ALUMINIUM PROFILE OF 35-50MM X 100MM (MIN 1.6MM THICK)
  - TIMBER DOOR FRAME SHALL BE 50MMX100MM HARDWOD
  - ALL DOOR PANEL THICKNESS SHOULD BE 40MM THICK SOLID CORE
  - ALL FRAMES EDGED SHALL BE TRIMMED 3MM
  - ALL WOODEDN COMPONENTS SHOULD BE WOOD STAINED FINISH
  - ALL GLAZING SHOULD BE OF 6MM UNLESS SPECIFIED
  - EXTERNAL UNITS MUST COMPLY THE FOLLOWING WEATHER CONDITIONS :
    WIND PRESSURE :200KG/SQM
    WATER TIGHTNESS : 25KG/SQM
  - ALL EXTERNAL FRAMES / WALL JOINTS MS BE SEALED WITH SILICON SEALANT AND THE EDGES TRIMMED WITH 12X12MM HARDWOOD BEADING FIXED TO FRAMED BY NAILS
  - ALL HARDWARE SHOULD BE PROVIDED FOR THE PERFORMANCE OF ALL FUNCTIONS OF THE UNITS
  - HINGES SHALL CONFIRM TO :
    1. DOOR SIZE MORE THAN 700X900MM
       WD : 125MM X 2SETS
       SD: 150MM X 3SETS
    2. DOOR SIZE LESS THAN 700X1900MM
       WD : 100MM X 2SETS
       SD: 125MM X 2SETS
  - LOCKS SHALL BE CYLINDRICAL WITH MASTER KEY SETS
  - DOOR KNOBS SHALL BE 1000MM ABOVE FFL

LEGEND:
CG - CLEAR GLASS
RG - REFLECTED GLASS
AL - ALUMINIUM
PVC - POLYVINYL CHLORIDE

DOOR & WINDOW SCHEDULE - 3

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	A 11 / 19

2D Symbol



V3	SUNSHADING
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINUM LOUVERS
LOCATION	CORRIDOR
QUANTITY	04 NOS
OPEN AREA	1.20 SQM

2D Symbol



V4	SUNSHADING
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINUM LOUVERS
LOCATION	CORRIDOR
QUANTITY	12 NOS
OPEN AREA	1.96 SQM

2D Symbol



V5	SUNSHADING
REMARKS	50mm THICK WHITE POWDER COATED (60 MICRONS) ALUMINUM FRAMED WITH ALUMINUM LOUVERS
LOCATION	CORRIDOR
QUANTITY	6 NOS
OPEN AREA	1.68 SQM

NOTE:-
- ALL DOORS & WINDOWS TO BE CHECKED ON SITE BEFORE FABRICATION.
- ALL DOOR & WINDOWS VIEWED FROM EXTERIOR, FOR DOOR SWING, REFER TO FLOOR PLANS.
- THE DOORS / WINDOWS WHICH DO NOT TOUCH THE BEAM SHALL HAVE A LINTEL BEAM (LB)
  ABOVE THE DOOR / WINDOW.
- FOR ALL THE WINDOWS PUT A SILL BEAM BELOW THE WINDOW (SB)
- FOR SAFETY PURPOSES REFER TO TECHNICAL SPECIFICATIONS FOR GLASS THICKNESS.
  - ALUMINIUM FRAME PROFILE SHALL BE 35-50MMX100MM (MIN 1,6MM THICK)
  - ALUMINIUM PANELS SHOULD BE MINIMUM 6MM THICK SINGLE SHEET WITHIN AN ALUMINIUM PROFILE OF 35-50MM X 100MM (MIN 1.6MM THICK)
  - TIMBER DOOR FRAME SHALL BE 50MMX100MM HARDWOD
  - ALL DOOR PANEL THICKNESS SHOULD BE 40MM THICK SOLID CORE
  - ALL FRAMES EDGED SHALL BE TRIMMED 3MM
  - ALL WOODEDN COMPONENTS SHOULD BE WOOD STAINED FINISH
  - ALL GLAZING SHOULD BE OF 6MM UNLESS SPECIFIED
  - EXTERNAL UNITS MUST COMPLY THE FOLLOWING WEATHER CONDITIONS :
    WIND PRESSURE :200KG/SQM
    WATER TIGHTNESS : 25KG/SQM
  - ALL EXTERNAL FRAMES / WALL JOINTS MS BE SEALED WITH SILICON SEALANT AND THE EDGES TRIMMED WITH 12X12MM HARDWOOD BEADING FIXED TO FRAMED BY NAILS
  - ALL HARDWARE SHOULD BE PROVIDED FOR THE PERFORMANCE OF ALL FUNCTIONS OF THE UNITS
  - HINGES SHALL CONFIRM TO :
    1. DOOR SIZE MORE THAN 700X900MM
       WD : 125MM X 2SETS
       SD: 150MM X 3SETS
    2. DOOR SIZE LESS THAN 700X1900MM
       WD : 100MM X 2SETS
       SD: 125MM X 2SETS
  - LOCKS SHALL BE CYLINDRICAL WITH MASTER KEY SETS
  - DOOR KNOBS SHALL BE 1000MM ABOVE FFL

LEGEND:
CG - CLEAR GLASS
RG - REFLECTED GLASS
AL - ALUMINIUM
PVC - POLYVINYL CHLORIDE

DOOR & WINDOW SCHEDULE - 4

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : A 12/ 19

			Ventilation Schedule			
Level	Zone Name	Area (sqm)	Opening	Required Opening	Designed Opening	Opening %
Ground Floor	Classroom 1	54.19	D04 X 2, W06 X 2	5.419	15.68	28.94
	Cleaner closet	4.35	Mechanical			
	Corridor	99.15	Open			
	Classroom 2	54.28	D04 X 2, W06 X 2	5.428	15.68	28.89
	Store	3.9	Mechanical			
	Toilet for disabled	6.82	Mechanical			
First Floor	Classroom 3	54.28	D04 X 2, W06 X 2	5.428	15.68	28.89
	Classroom 4	54.28	D04 X 2, W06 X 2	5.428	15.68	28.89
	Cleaner closet	11.57	Mechanical			
	Corridor	102.97	Open			
	Store	7.3	Mechanical			
	Toilet (F)	11.07	W02	1.107	1.84	16.62
	Toilet (M)	11.15	W02	1.115	1.84	16.50

VENTILATION SCHEDULE

NTS

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT

R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : A-15/ 15

1. General notes

1.1.Do not scale the drawings. All dimensions shall be read from the drawing or computed.Elevations are in millimeters, distances and reinforcement bar sizes are in millimeters.

1.2. In the interpretation of these drawings, indicated dimensions shall govern and distances or sizes shall not be scaled for construction purposes.

1.3. The contractor shall coordinate with the ar, se, ee and other utility and equipment plans for the exact size, number and locations of all sleeves or openings through floor slabs, beams and walls. Any discrepancies or conflict in the setting out lines, levels, details, locations, sizes, reinforcement etc. Of the structural member shall be brought to the attention of the engineer prior to commencement of work.

1.4. All reinforced concrete work shall be done in accordance with the british structural code bs 8110 or ec-en2 building code.

1.5. All structural steel work shall be done in accordance with the british structural code bs5950 parts 1to 9 and ec-en3 in so far as they do not conflict with the local building code requirements.

1.6. All slabs, beams and other structural elements which are not indicated, detailed, designated or inadvertently omitted but are necessary to be coordinated with architectural and other allied engineering plans as well as to complete the structural works in accordance with the intent of the plans and specifications shall be brought up during pre-bids/meetings/negotiations. It is understood that the contractor has provided and included all these items in his bid.

1.7. The contractor shall produce shop drawings and schedules as required for completion of the works and record drawings of the as-built and builder works for the consultant's approval.

1.8. Contractor shall do full coordination between structural, architectural and mep drawings in wet areas to allow for drainage pipes.

1.9. All discrepancies shall be brought to the attention of the consultant engineer proceeding with the work on site.

1.10. All materials to be used in conjunctions shall comply with the requirements of the specified codes, standards and ordinance of relevant building authorities unless noted otherwise in the project specification and /or drawings.

1.11. All dimensions and levels shown on the drawings shall be verified by the contractor . Any discrepancies shall be brought to consultant's attention prior to construction.

1.12. The contractor shall ensure that during construction, no part of the structure is overstressed by excessive construction loads until their completion. Temporary bracing and propping to be provided were required.

1.13. Once the excavation is done to a specified depth, the bearing capacity of the soil shall be confirmed by relevant test, if the value is less than the design bearing capacity the engineer is to be informed immediately.

1.14. The contractor shall submit a method statement for all elements of work and shall not proceed until consultant's written approval is given. The method statement shall provide the contractor's preferable options where such options are available.

1.15. The contractor shall comply with all requirements of the local regulations and requirements of all concerned authorities.

1.16. Quality of concrete finish for all non-plastered columns and beams is to be in accordance with- fair faced concrete as reflected on the architectural drawings and specifications.

1.17. Any structural requirements specified by relevant authorities, which are not covered in notes and specifications are assumed to be duly considered by the contractor.

1.18. All typical details and notes shown on drawings shall apply unless noted otherwise. Typical detail may not necessary be indicated on the plans but shall still apply as shown or described in the details where particular details are noted on the drawings the specified details shall be used.

1.19. The design life of the structure of this project shall maintain a minimum of50 years life period. The primary structural components are to be designed and detailed to satisfy this requirement. Concrete mix supplier shall submit a life cycle analysis which reflect a 50 years design life without maintenance, inspection and repair requirement during this period.

2. Concrete

2.1. All concrete works shall conform to the bs8110 or ec-en, a grade of c25/30 indicates that concrete shall have a fcu compressive strength of 30n/mm2 established from test cubes at 28 days equivalent to a compressive strength of 25n/mm2 established from cylinder tests at 28 days.

concrete mix design shall comply with bs8500-1:2006 as follows:

Miz Number	1	2	3	4
Grade	C30/37	C25/30	C25/30	C16/20
Min cement content (kg/m^3)	380	340	340	300
Cement Type	SRC	SRC / OPC	OPC	SRC / OPC
Max free W/C ratio	0.4	0.45	0.45	0.55
Slump	75 ± 25	75 ± 25	75 ± 25	100 ± 25
Aggregate	20	20	20	20

mix 1 - used in reinforced concrete works for structures at sea/exposed to sea, water retaining structures and tank structures.

mix 2 - used in reinforced concrete works for ground level and below (sub-structutre) or any reinforced concrete works in contact with soil or water.

mix 3 - used in reinforced concrete works above ground flr lvl (superstructure) for horizontal members (beams/slabs) and vertical members (columns/walls).

mix 4 - used for plain concrete blinding and mass fill.

2.2. Contractor shall implement a trial mix in accordance with the project specifications & authority requirements. Trial mix results shall be submitted for engineer's review & approval prior to commencing concreting.

2.3. Contractor shall submit the details of additives, plasticizers, micro silica, curing compounds, waterproofing agents, etc. Application should follow strictly the manufacturer recommendation. It is contractors responsibility to ensure that all constituents of concrete are compatible to each other.

2.4. Maximum percentage (by weight) of salt contents permissible in aggregates used for concrete, hollow blocks & hourdi blocks, etc, shall be as follows:

a) acid soluble chlorides in aggregate - (fine 0.03%, coarse 0.02%)

b) acid soluble sulphate in aggregate - (fine 0.3%, coarse 0.2%)

2.5. Concrete shall be cured by an approved means in accordance with the specifications.

2.6. Aggregates shall be from approved source and in accordance with the specifications.

2.7. Openings, sleeves:

a) no holes, sleeves or penetrations be placed vertically or horizontally through beams unless approved by the engineer.

b) no holes to be made in slabs unless approved by the engineer.

2.8. Construction joints:

a) the contractor shall submit to the engineer for approval a plan marked up showing the location of all construction joints

b) horizontal construction joints shall not be made in beams, unless approved by the consultant or engineers.

c) vertical construction joints may be located at midspan of slabs or beams after reviewed and approved by the engineers.

d) contractor shall submit shear friction and the additional required reinforcement calculation of construction joint at any location) for engineers review and approval.

3. Reinforcement

3.1. The reinforcement used in the reinforced concrete shall be round, deformed type 2 bars marked as (t) to indicate high yield strength of 460n/mm2 to bs4449 or type 500b to ec-en. The carbon equivalent of rebars should not exceed 0.51 for grade 460.

3.2. Reinforcement details shown are indicative. The contractor shall prepare detailed shop drawings & full bar schedules in accordance with the design drawings and shall be cut and bent in accordance with bs 8666 and aci 315-09 for the engineer's approval at least four weeks prior to commencement of reinforced concrete work and after coordinating with all concerned parties.

3.3. Lap lengths and anchorage lengths of reinforcement shall be as per bs 8110 and ec en. Additional lapping if required to be provided with engineer's approval. The minimum lap length of reinforcement shall be the maximum of (45 bar dia in general and 50 dia for tension) or the values of the table a.

Table a : schedule of lap splices

Bar dia	lap splices length (mm)
10	500
12	600
16	800
20	1000
25	1250

3.4. Spacer bars in beams shall be a minimum t25 or the size of bar if greater at 1000mm c/c; chairs in slabs shall be a minimum t12@1000mm c/c; and minimum ties in walls shall be t8@1000mm c/c.

3.5. Clear cover to reinforcement including links, stirrups, and ties shall be as follows:

A) structure in contact with ground

Footings = 60mm

Wall and column = 50mm

Ground beam = 50mm

Slab at ground level = 50mm

B) super structure

Columns = 40mm

Beams = 35mm

Slabs = 30mm

Walls = 40mm

All concrete elements in contact with water/splash zone = 50mm

3.6. Reinforcement bars to be cut, bent or adjusted to clear all openings and interfering structures to suit at site to the approval of the consultant or engineer.

3.7. For holes in slabs up to 300x300 sq., reinforcement is to be cut and replacement bars fixed adjacent to the hole extending 50x bar diameter beyond the hole.

4. Fire resistance

4.1. All structural concrete members between units on boundaries are designed to maintain fire resistance of 2 hours.

Genaral Notes 1

1:20

5. Cracking

5.1. The cracking of the structural concrete in general is restricted to 0.30mm.

6. Earthwork & foundations

6.1. Foundation detail design is based on the assumed safe allowable bearing capacity has been taken as 150kpa. The actual requirement for the foundation design is to be verified based on final geotechnical report for the project.

6.2. Excavations for foundations down to formation level shall be carried out by mechanical means, except for the last 100mm of excavation which is to be carried out by manual methods and recommended by geotechnical consultant.

6.3. The formation level of foundation is to be inspected and approved by the geotechnical engineer before commencement of the work.

6.4. Engineering fill (unless specified otherwise as a higher quality material) shall be selected well graded granular material approved by the engineer with a minimum soaked cbr of 15% compacted not exceeding 250mm in layers to 95% maximum dry density as per geotechnical investigation report recommendations in accordance with the specification. However, a minimum cover of 250mm back fill material shall be provided at the top of foundations below the blinding to cast against.

6.5. Efficient site drainage during and after construction of the project should be provided by the contractor.

6.6. Site inspection by a qualified engineer should be carried out after completion of the excavation works and after preparation of the proposed foundation level to ensure that the contact surface is free from any loose/soft layer and properly prepared for the foundation.

7. Concrete workmanship

7.1. All concrete without plaster shall be fair finish unless noted otherwise.

7.2. All concrete surface to have plaster are to be hacked to have an adequate surface key.

7.3. All concrete is to be cured by an approved method-water pounding or curing compound.

7.4. All types of construction joints in concrete shall be at a specified locations and approved by the engineers.

7.5. All substructure concrete works shall be protected with water proofing as per standard details & specifications.

7.6. All concrete shall be compacted using a mechanical vibration process.

7.7. 25x25mm chamfers to external corners and edges shall be provided in accordance with specifications and directed by the engineer.

8. Structural steel

8.1. All structural steel works shall be in accordance with bs 5950 parts 1 to 9 or ec-en3.

8.2. Maximum dimension of holes shall be in accordance with bs 5950 : part 1 : 2000 table 35, unless indicated otherwise.

8.3. The contractor shall provide whatever temporary ties or bracing necessary for a safe and proper erection of the steel structures.

8.4. Welding shall comply with bs en 1011-1: 2009, bs en 1011-2 : 2001 and bs bs en 1011-8 : 2004.

8.5. Contractor shall do a detailed design for aluminum shades and to submit full design calculations and detailed shop drawings for all steel sections and connections to the engineer for approval prior to commencement of fabrication.

8.6. All rolled products and plates shall conform to bs en 10025-2. Cold form welded structural hollow sections shall conform to bs en 10219-1. Hot finish hollow sections shall conform to bs 10210-1 unless noted otherwise on drawings.

8.7. All connections shall be made with minimum 2nos. Galvanized grade 8.8 to bs 3692 with a minimum diameter of 20mm and minimum yield strength of 627mpa and minimum ultimate strength of 765mpa and electrodes to bsd 639, unless noted otherwise.

8.8. Unless noted otherwise on the drawings, all connections shall be in accordance with the following minimum requirements:

A) all welds shall be at least 6mm continuous fillet welds all around.

B) all structural bolted connections should be galvanized minimum 85 micron and with a minimum of 2 bolts per connection. Purlin bolts shall be in accordance with the suppliers recommendations.

C) all gusset plates shall be at least 4mm thick.

D) all cap plates shall be at least 4mm thick.

E) all base plates shall be at leat 4mm thick.

8.9. As minimum all structural steel members shall be shot blasted to sa 2.5, galvanized, primed & painted as below unless noted otherwise:

A) hot galvanization (dft 200micron)

B) primer coat to contain 2 coats of zinc rich epoxy primer (dft 75 micron)

C) top coat to contain 2 coats of polyurethane enamel paint (dft 125 micron)

8.10. All structural steel work shall be corrosion protected in accordance with the structural specifications.

8.11. All steel should conform to the following:

A) shs, rhs and chs sections bsen 10210 s275 fy=275mpa

B) all angles and channels u.n.o bsen 10025 s275 fy=275mpa

8.12. All steel columns to be central on grids or equally spaced between grids unless noted otherwise.

8.13. All steel beams to be central on grids or equally spaced between grids unless noted otherwise.

8.14. All steel dimensions are to center line of section unless noted otherwise.

8.15. All bracing is to be set out on the centroids of bracing members and on the center line of beams and columns unless noted otherwise.

8.16. Where bracing is shown offset from center of members the contractor shall design and provide all necessary stiffeners.

8.17. Contractor to provide all leader railing as required to support free edges not trimmed with cold formed or mild steel work. To be provided in accordance with architect 's drawings.

8.18. Location of any connections, splices not shown in the drawings shall be submitted with design for engineer's approval. No splices shall be made unless shown in the drawings and as approved by the engineers.

8.19. Contractor shall do a full coordination between architecture and structural drawings for the steel support for shade elements, locations and sizing connections with structural concrete elements and sections. Care shall be taken to prevent dissimilar metal corrosion.

9. Masonry blocks

9.1. Design and construction of all blocks shall comply with bs 5628 : parts 1.2 & 3 : 1992 or en-ec6. The contractor shall submit a construction method statement prior to commencing the works.

9.2. Wall ties in accordance with bs 1248 - cp 121 part 1.73.

9.3. All block wall joints to manufacturers specifications.

9.4. All block work walls are to be considered as non-load bearing partitions unless noted otherwise in drawings.

9.5. Block walls shall be reinforced horizontally and vertically as per manufacturers requirements.

9.6. Masonry wall mechanical properties

young's modulus = 3.5e+006 kn/m2
poisson's ratio = 0.25
density = 20kn/m3
min.compressive strength = 3.5 mpa

10. Design & loading

10.1. Consultant design

design and construction of reinforced concrete structural members, shall be in accordance with bs8110 & ec-en2 and the structural steel members to bs 5950 & ec-en3.

10.2. Contractor design

the contractor is responsible for the design of all temporary works. (shoring for excavation, signage... Etc) and the following items of permanent secondary works. (subjected to engineers review and approval)

a) precast concrete elements
b) architectural facade and support steelwork
c) non load bearing feature columns
d) all secondary steel works
e) structural steelwork connections
f) structural support for mep services
g) shade structures
h) balustrade and crash barrier
i) structural glass
j) interior signage

the design of the primary structure is considering the interfaces with these structures) loading reactions, opening...etc.) And were detailed to accommodate these elements into the design.
the contractor shall submit a full detail design for the wall and boundary wall foundation, also the contractor to do
full coordination between the structural foundation for villas (including the water tanks, and the boundary wall for clashes, the contractor shall produce shop drawings for
the boundary walls for engineer's approval.

10.3. Loading

a) superimposed (dead loads & live loads) as per bs 6399 or en-ec1.
b) self-weight & densities as per bs 648 or en-ec1.
c) wind loads as per bs 6399 or en-ec1 (mean wind speed = 25m/s).

11. Timber

11.1. All timbers shall be in accordance with bs 5268 or ec-en5

11.2. All timber members sizes are indicative. Contractor shall coordinate with supplier and submit detail designs for all prefab timber structure for approval.

Genaral Notes 2

1:100

Notes:

1. First stirrups location shall be s/2 from the face of the column/ support.

2. Place one b bar in each bottom corner and one t bar in each top corner of the stirrup cage.

3. Condition shown is at columns. Where beams and girder intersect, use typical interior girder section.

4. All bottom bars and top bars shall be placed in one layer unless two layers are noted in the beam schedule. Where to layers are noted provide 25 mm clear between layers. If two layers are noted place bar b1 above bar b and bar t above t1.

5. Length of exterior top bars are given only when straight bar occurs otherwise hooked bars are required.

6. Where a member is supported by a column, but has another member running perpendicular to it at the same column, the first stirrup spacing shall start from the face of the column and not from the face of the transverse beam.

7. Top & bottom reinforcement lapping of both main rebars can be ignored if the main rebars at left and right side of lapping location are identical.

8. For 'column width less or equal 2m l*="column width'/2. For 'column width' greater than 2m, l*=1m

Supplementary abbreviations:

B1 - continuous bottom bars.
B2 - additional bottom bars
CE - cantilevered end
D - depth of member, mm
EE - each end
EF - each face
FL - full length
EW - each way
H - aci standard hook
ITB - interior top bar
LE - left end
LG - length
P - paired stirrups
RE - right end
REM - remainder
S - side bars
T1 - top bars at internal supports
T2 - top bars at mid-span
T3 - top bars at end support
W - width of member, mm



SIMPLE BEAM DETAILS

NTS



TYPICAL CANTELEVER BEAM FROM COLUMN

NTS

NOTES :
Incase of t1 & t3 have same diameter splice to be omitted.



TYPICAL CANTELEVER BEAM CONTINUOUS

NTS



CONTINUOUS BEAM DETAILS

NTS

Genaral Notes 3

1:100



FOUNDATION PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

Foundation Details:

	Dimensions	Reinforcement	Foundation depth
F1	1900X1900X350	T12@125C/C B/W (B)	1200mm
F2	1700X1700X350	T12@150C/C B/W (B)	1200mm
F3	1450X1450X350	T12@150C/C B/W (B)	1200mm
F4	1300X1300X350	T12@150C/C B/W (B)	1200mm
F5	1150X1150X350	T12@150C/C B/W (B)	1200mm
F6	1000X1000X350	T10@150C/C B/W (B)	1200mm

Ground Slab = 100mm thick RC slab on fill reinforced with T10@200C/C (B/W)

All Footings are to be laid on top of 50mm thick lean concrete
Add waterproofing admixture and apply waterproofing to all substructure (below ground elements)

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-01 / 18



COLUMN LAYOUT PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-02 / 18



FIRST FLOOR BEAM PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-03 / 18

175 mm

155 mm

Bottom Reinforcement:

Bottom Additional Reinforcement:

Top Reinforcement:

Top Distribution steel:

T12@150c/c B/W (Not Shown)
T12@150c/c B/W (As shown)
T12@150c/c (As shown, unless stated)
T12@150c/c (Unless stated)



FIRST FLOOR SLAB REINFORCEMENT PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT

R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : E-04 / 18



ROOF BEAM LEVEL 1

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-05 / 18



Notes:

WCB (Wall cast beam cast on top of wall)

ROOF BEAM LEVEL 2

SCALE 1:100

0 0.5 1 2 3 4 5

Notes:

WCB (Wall cast beam cast on top of wall)

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-06 / 18



ROOF TRUSS

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-07 / 18



ROOF FRAMING PLAN

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-08 / 18

Foundation Details:

	Dimensions	Reinforcement	Foundation depth
F1	1900X1900X350	T12@125C/C B/W (B)	1200mm
F2	1700X1700X350	T12@150C/C B/W (B)	1200mm
F3	1450X1450X350	T12@150C/C B/W (B)	1200mm
F4	1300X1300X350	T12@150C/C B/W (B)	1200mm
F5	1150X1150X350	T12@150C/C B/W (B)	1200mm
F6	1000X1000X350	T10@150C/C B/W (B)	1200mm

Ground Slab = 100mm thick RC slab on fill reinforced with T10@200C/C (B/W)

All Footings are to be laid on top of 50mm thick lean concrete
Add waterproofing admixture and apply waterproofing to all substructure (below ground elements)

FOUNDATION DETAILS

Foundation Notes
1:100



Plan View

Sectional View

TYPICAL PAD FOOTING DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1

STRUCTURAL DETAILS

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1



NOTE:
All cover blocks shall be casted using grade C 25 / 30 concrete with 5-10 mm aggregates

For slab, rebar spacer chairs spacing shall be minimum 1m spacing or 1 no. per 1 sqm

GROUND SLAB DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1



COLUMN DETAILS

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1



TB1

TIE BEAM DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1





Lintel / Sill Beam Detail

B3

RB1



SRB

WCB

SRB (Sloping roof beam cast on top of wall at gable level)

(Cast on top of wall)

BEAM DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : E-09 / 18





Note:

* Concrete surfaces shall be thoroughly cleaned with water & applied with mastercast 141 or equivalent bonding mortar prior to plastering.
* Plastering mortar mix shall be 1:4 (cement: sand) ratio.
* Plaster mix shall be modified using fibre wool & mastercast 141 or equivalent plasticisers as per manufacturer's specification.
* Height of placing blocks shall be maximum 1.2m per day.
* After initial coat of plastering, water curing shall be provided for minimum 3 days & after final coat water curing shall be provided for 7 days.

TYPICAL WALL CONSTRUCTION DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : E-10 / 18



LT1

LINTELS OVER ALL DOORS, WINDOWS
(THAT DOES NOT RISE TO BEAM LEVEL)
LT1 FOR WINDOWS < 1.5M



LT2

LINTELS OVER ALL DOORS, WINDOWS
(THAT DOES NOT RISE TO BEAM LEVEL)
LT2 FOR WINDOWS > 1.5M & <3.0M



LT3

LINTELS OVER ALL DOORS, WINDOWS
(THAT DOES NOT RISE TO BEAM LEVEL)
LT3 FOR WINDOWS > 3.0M & <6.0M

Lintel Beam Detail
1:20



LB1

Sill Beam Detail
1:20



Typical Window
Construction Detail

WINDOW CONSTRUCTION DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : E-11 / 18



ELEVATION

SCALE 1:20

NOTE:-
FLOOR TO FLOOR HEIGHT VARIES AND WILL BE SUBJECTED TO CHANGES

RAILING DETAILS

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1



SECTION

SCALE 1:20

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-12 / 18



Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE
CLIENT MINISTRY OF EDUCATION
ARCHITECT :
ENGINEER :
DRAWN :
CHECKED :
SCALE : AS GIVEN
DATE : 13.10.2021
DWG NO : S-12 / 18



ELEVATION D





ELEVATION C



SECTION E-E

DETAIL - 2
MAIN ENTRANCE RAMP DETAILS

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE

CLIENT MINISTRY OF EDUCATION

ARCHITECT :

ENGINEER :

DRAWN :

CHECKED :

SCALE : AS GIVEN

DATE : 13.10.2021

DWG NO : E-14 / 18



STAIR REINFORCEMENT DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1



1. Post top, bottom&1.2m vertical support members to be75x75x2.5mm thick GI SHS(2 coats of anti corrosive paint with approved finishing color coat

2. Handrail material to be50mm Ø 2.5mm thick GI CHS with2 coats of anti-corrosive paint and approved finishing coat

3. Step: 300mm

4. Raise:152mm

STAIR RAILING DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1

Issue	Date	Description

AMMENDMENTS.

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-15 / 18



TRUSS FIXING DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1



TRUSS DETAIL

SCALE 1:20

0 0.1 0.2 0.4 0.6 0.8 1

Notes:

All the CHS shall have minimum yield stress of 275MPa
All welds shall be 6mm thick full parameter fillet welds
All truss ends shall be capped with 6mm plates
All truss members shall be protected with anti corrosive coatings

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-16 / 18



TOILET PLAN (MALE & FEMALE)

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION A3

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION A2

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION A1

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION A4

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT

R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	E-17 / 18



DISABLE TOILET FLOOR PLAN

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION B4

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION B2

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION B1

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5



ELEVATION B3

SCALE 1:50

0 0.25 0.5 1 1.5 2 2.5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-18 / 18

BUILDING SERVICES DRAWINGS OF

PROPOSED 02 STOREY BUILDING

R. ATOLL EDUCATION CENTRE
2 STOREY BUILDING

Ministry Of Education

TABLE OF CONTENTS

DRAWING No.	TITLE	REVISION No.	DATE	REMARKS
S E R V I C E S		---	---	---
S - 01 /11	GROUND FLOOR POWER & ACV LAYOUT	---	---	---
S - 02 /11	FIRST FLOOR POWER & ACV LAYOUT	---	---	---
S - 03 /11	GROUND FLOOR FDP LAYOUT	---	---	---
S - 04 /11	FIRST FLOOR FDP LAYOUT	---	---	---
S - 05 /11	GROUND FLOOR LIGHTING LAYOUT	---	---	---
S - 06 /11	FIRST FLOOR LIGHTING LAYOUT	---	---	---
S - 07 /11	GROUND FLOOR PLUMBING LAYOUT	---	---	---
S - 08 /11	FIRST FLOOR PLUMBING LAYOUT	---	---	---
S - 09 /11	GROUND FLOOR DRAINAGE LAYOUT	---	---	---
S - 10 /11	FIRST FLOOR DRAINAGE LAYOUT	---	---	---
S - 11 /11	ROOF DRAINAGE LAYOUT	---	---	---



GROUND FLOOR POWER & ACV LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- 13A Twin Socket
- 13A Power Socket
- Distribution Board
- 13A Power Socket in Weatherproof Polycarbonate Enclosure
- 15A Switched Socket @ H.L.
- ISB — Internet Switchboard
- Emergency Light
- WS — Wall Mounted Speaker
- M — Electricity Meter
- Computer Network Twin Outlet
- HDMI Socket
- Ceiling Mounted Exhaust Fan 90m3/hr
- Wall Mounted Exhaust Fan
- HL. — High Level
- Computer Network Outlet

- —— 82Ø PVC Duct For Tel./Internet Cable Lead In Below Ground Slab
- —— Main Incoming Cable For Power In 110Ø PVC Duct Below Ground Slab

Notes:
- All Twin Sockets At 300mm From F.F.L. Except Stated Otherwise
- All Computer, Telephone Points At 300mm From F.F.L.
- All electrical components shall be connected to respective Distribution Box in the same area as the component.
- All electrical components in common areas, corridors and staircase should be connected to Common Area DB
- Wall Speaker shall be connected to Public address system of school

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-01 / 11



FIRST FLOOR POWER & ACV LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- 13A Twin Socket
- 13A Power Socket
- Distribution Board
- 13A Power Socket in Weatherproof Polycarbonate Enclosure
- 15A Switched Socket @ H.L.
- ISB — Internet Switchboard
- Emergency Light
- WS — Wall Mounted Speaker
- M — Electricity Meter
- Computer Network Twin Outlet
- HDMI Socket
- Ceiling Mounted Exhaust Fan 90m3/hr
- Wall Mounted Exhaust Fan
- HL. — High Level
- Computer Network Outlet

- 82Ø PVC Duct For Tel./Internet Cable Lead In Below Ground Slab
- Main Incoming Cable For Power In 110Ø PVC Duct Below Ground Slab

Notes: -
- All Twin Sockets At 300mm From F.F.L. Except Stated Otherwise
- All Computer, Telephone Points At 300mm From F.F.L.
- All electrical components shall be connected to respective Distribution Box in the same area as the component.
- All electrical components in common areas, corridors and staircase should be connected to Common Area DB
- Wall Speaker shall be connected to Public address system of school

- AC — Wall Mount Air Conditioner
- CU — Outdoor Condensing Unit
- Refrigerant Pipes
- 25Ø Condensate Drain Pipe
- 40Ø Condensate Drain Riser Pipe
- Ceiling Mounted Exhaust Fan 90m3/hr
- Wall Mounted Exhaust Fan

Notes: -

Where Condensate Drain Pipes Are Connected To Wash Basin Or Kitchen Sink, 25 Ø Condensate Drain Pipe Is Extended In 32 Ø Flex Conduit Into 40 Ø Waste Pipe Of Respective Basin Or Sink

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-02 / 11



GROUND FLOOR FDP LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- CO_2 Extinguisher (load: 2kg) In Polycarbonate Enclosure
- H_2O Extinguisher (load: 9L) In Polycarbonate Enclosure
- Manual Call Point
- SD — Smoke Detector
- Beacon
- Sounder Bell
- 2.5mm² Fire Retardant Low Smoke (FRLS) Cables In FRLS Conduits running through screed
- 2.5mm² Fire Retardant Low Smoke (FRLS) Cables In FRLS Conduits running at ceiling level
- EXIT — Exit Sign
- FACP — Fire Alarm Control Panel

Issue	Date	Description

AMMENDMENTS.

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-03 / 11



FIRST FLOOR FDP LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- CO_2 Extinguisher (load: 2kg) In Polycarbonate Enclosure
- H_2O Extinguisher (load: 9L) In Polycarbonate Enclosure
- Manual Call Point
- SD — Smoke Detector
- Beacon
- Sounder Bell
- 2.5mm² Fire Retardant Low Smoke (FRLS) Cables In FRLS Conduits running through screed
- 2.5mm² Fire Retardant Low Smoke (FRLS) Cables In FRLS Conduits running at ceiling level
- EXIT — Exit Sign
- FACP — Fire Alarm Control Panel

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-04 / 11



GROUND FLOOR LIGHTING LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- Ceiling Light (18W)
- Ceiling Light (12W)
- Recessed Ceiling Light (12W)
- Ceiling Down Light (18W) - Weather Proof
- 100W, HPS, Wall Mounted Light,IP 65
- 3 Ft Led Tube Light
- Ceiling Recessed Spot Light (3W)
- 1 2 3 4 5 Light Switch (1 Gang - 5 Gang)
- F Ceiling Fan Switch With Controller
- Ceiling Mounted Exhaust Fan 90m3/hr
- Wall Mounted Exhaust Fan
- 42" To 48" Ceiling Fan

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-05 / 11



FIRST FLOOR LIGHTING LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- Ceiling Light (12W)
- Recessed Ceiling Light (12W)
- Ceiling Down Light (18W) - Weather Proof
- 100W, HPS, Wall Mounted Light,IP 65
- 3 Ft Led Tube Light
- Ceiling Recessed Spot Light (3W)
- 1 2 3 4 5 Light Switch (1 Gang - 5 Gang)
- F Ceiling Fan Switch With Controller
- Ceiling Mounted Exhaust Fan 90m3/hr
- Wall Mounted Exhaust Fan
- 42" To 48" Ceiling Fan

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-06 / 11



GROUND FLOOR PLUMBING LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- 25Ø Cold Water Supply Pipes Running Underground
- 20Ø Cold Water Supply Pipes Running In Wall
- 20Ø Cold Water Supply Pipes Running Above False Ceiling
- 20Ø Cold Water Supply Pipes Running Underground
- 25Ø Ground Water Supply Pipes
- 16Ø Cold Water Supply To Basin Faucet
- 16Ø Cold Water Supply To Bidet Shower
- 16Ø Cold Water Supply To Cistern
- Gate Valve
- Rise In Wall
- Drop In Wall
- Angle Valve with cap for Ground Water Supply
- False Ceiling

Notes: -

-All Cold Water Pipes Should Be PVC
-All Hot Water Pipes Should Be PPR

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-07 / 11



FIRST FLOOR PLUMBING LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- 25Ø Cold Water Supply Pipes Running Underground
- 20Ø Cold Water Supply Pipes Running In Wall
- 20Ø Cold Water Supply Pipes Running Above False Ceiling
- 20Ø Cold Water Supply Pipes Running Underground
- 25Ø Ground Water Supply Pipes
- 16Ø Cold Water Supply To Basin Faucet
- 16Ø Cold Water Supply To Bidet Shower
- 16Ø Cold Water Supply To Cistern
- Gate Valve
- Rise In Wall
- Drop In Wall
- Angle Valve with cap for Ground Water Supply
- False Ceiling

Notes: -

-All Cold Water Pipes Should Be PVC
-All Hot Water Pipes Should Be PPR

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-08 / 11



Notes: -

-All Drainage Pipes Should Have At A Slope Of 1/150
-All Floor Drains Should Have 'P' Traps

Legend

- Floor Drain
- Floor Gully
- 110Ø Soil Pipe (uPVC Pipe)
- 110Ø Soil Vent Pipe (uPVC Pipe)
- 82Ø Waste Pipe (uPVC Pipe)
- 82Ø Waste Vent Pipe (uPVC Pipe)
- 40Ø Waste Pipe (uPVC Pipe)
- 63Ø Manhole Vent Pipe (uPVC Pipe)
- 110Ø Rain Water Pipes (uPVC Pipe)
- Bottle Trap
- Rodding Eye
- Gully Trap
- Manhole
- False Ceiling

GROUND FLOOR DRAINAGE LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-09 / 11





DETAIL A-A

Legend

- Floor Drain
- Floor Gully
- 110Ø Soil Pipe (uPVC Pipe)
- 110Ø Soil Vent Pipe (uPVC Pipe)
- 82Ø Waste Pipe (uPVC Pipe)
- 82Ø Waste Vent Pipe (uPVC Pipe)
- 40Ø Waste Pipe (uPVC Pipe)
- 63Ø Manhole Vent Pipe (uPVC Pipe)
- 110Ø Rain Water Pipes (uPVC Pipe)
- Bottle Trap
- Rodding Eye
- Gully Trap
- Manhole (MH)
- False Ceiling

Notes: -

-All Drainage Pipes Should Have At A Slope Of 1/150
-All Floor Drains Should Have 'P' Traps

FIRST FLOOR DRAINAGE LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-10 / 11



ROOF DRAINAGE LAYOUT

SCALE 1:100

0 0.5 1 2 3 4 5

Legend

- Floor Drain
- Floor Gully
- 110Ø Soil Pipe (uPVC Pipe)
- 110Ø Soil Vent Pipe (uPVC Pipe)
- 82Ø Waste Pipe (uPVC Pipe)
- 82Ø Waste Vent Pipe (uPVC Pipe)
- 40Ø Waste Pipe (uPVC Pipe)
- 63Ø Manhole Vent Pipe (uPVC Pipe)
- 110Ø Rain Water Pipes (uPVC Pipe)
- Bottle Trap
- Rodding Eye
- Gully Trap
- MH Manhole
- False Ceiling

Notes: -

-All Drainage Pipes Should Have At A Slope Of 1/150
-All Floor Drains Should Have 'P' Traps

Issue	Date	Description
AMMENDMENTS.		

PHYSICAL FACILITIES DEVELOPMENT SECTION
MINISTRY OF EDUCATION,
MALE',
REPUBLIC OF MALDIVES

PROJECT
R.ATOLL EDUCATION CENTRE
02 STOREY BUILDING

PROJECT REFERENCE	
CLIENT	MINISTRY OF EDUCATION
ARCHITECT :	
ENGINEER :	
DRAWN :	
CHECKED :	
SCALE :	AS GIVEN
DATE :	13.10.2021
DWG NO :	S-11 / 11