

DOOR WINDOW SCHEDULE - SH. MAROSHI HEALTH CENTER RENOVATION

1:50

DL 1	Main entrance Door Leaves
<div><div></div><div><div></div><div>955</div></div><div><div></div><div>2045</div></div></div>	
LOCATION	MAIN ENTRANCE
QUANTITY	02
FRAME	EXISTING
PANEL	TREATED SOLID TIMBER (READY MADE-DOOR PANEL)
FINISH	SEAMASTER/SIGMA OR EQUIVALENT ENAMEL PAINT
HINGE	PARLAMENT HINGES SINGLE SIDE OPENING
LOCK	STATE MAKE (CYLINDRICAL TOILET LOCK)
NOTE	ALL MEASUREMENTS TO BE CHECKED ON SITE

ALL MEASUREMENTS TO BE CHECKED ON SITE BEFORE FABRICATION