

[illegible]

نمبر	TES/2019/G - 031	
No:		
پراجیکٹ	Supply and Installation of Turf in 22 Islands Football Grounds	
Project:		
تاریخ	12 th December, 2019	
Issued Date		
پاجوں کی تعداد	BoQ: -00	نقشوں کی تعداد
No. of Pages: -03		Drawings: - 00

Please include this amendment when submitting the bid. **بموجب هذا التعديل يجب ان يتضمن المزايد هذا التعديل عند تقديم المزايدة.**

➤ **Find the Responses to the Queries raised**

1. What is the Spreading rate per Sq.m for Infill Materials Silica Sand and rubber?

There is number of FIFA preferred and FIFA Licensed products, with different technical specification and methods of installation, one of our requirement is the product supplied must be FIFA preferred or Licensed.

2. Goal foundation type may be provided whether RCC or PCC?

PCC, concrete block with ground socket with drain hole.

3. Goal Post & Corner Post Specification may be provided such as material type (Galvanized Iron, Mild Steel, and Stainless Steel) and Section wall thickness.

Reinforced aluminum section with durable powder coated finish designed for heavy outdoor use. BS EN 748 Complain

4. Goal post & Corner post what type of primer to be applied.

Durable powder coated finish Goal post and Poles: Weatherproof PVC with Flags: Ultra-durable nylon.

5. Goal net requirement Specification?

Polyethylene braided into 5" sq. mesh

6. Specify the Substitute bench material types Aluminum, Steel, Stainless steel and its sheet & flat thickness?

Heavy duty aluminum 3mm (minimum) thick shatter proof clear Microloan on end panels.

7. Type of material for Substitute Bench fastener Specs?

Treated wood slatted seating or UV treated HDPE seats that feature weatherproof properties for additional durability

8. What is the limitation of Vertical deformation of surface?

Pre-Condition 4mm - 11mm



9. What is the limitation of Surface regularity?

FIFA Quality <10 mm

10. Provide the details of existing base was made what type of material whether Coral sand or Crushed aggregate base course and also provide its completed test reports and cross sectional details?

Reclaimed soil compacted

11. What is the duration of Project?

Contractor proposed duration will be evaluated during the bid evaluation.

12. In the bidding Documents Section ix – 28.3 Warranty period mentioned as 3 years, the warranty mentioned in the document for turf?

Product must be FIFA certified

13. Adhesive component recommended specification and confirmation ASTM code?

Bi Component Adhesive (Special for Artificial Turf).

14. Ground drain arrangement to be provided or not?

Drainage is around the pitch area (400 mm gutter) Gutter system

15. Geo textile to be provided or not?

No

16. Whether sub base work is included or Not.

Sub base construction is not included

17. Whether a separate document has to be made for each lot.

Reference to tender documents

18. Do we need to test the concrete compressive strength?

Sub base is reclaimed soil sub base

19. There is no information on the sub base? Does the contractor need to do any work related to sub base.

No Sub base construction will be required.

20. Does the contractor's scope include any responsibility for drainage work?

Scope of the work does not include drainage work.

21. Does the contractor's scope include any responsibility for landscaping work? Such as paving the area between the boundary wall and turf?

Scope of the work does not include landscaping.

22. After completion of work does the contractor need to conduct any quality assurance test?

Such as infill depth ball roll, pile height, ball rebound> if so will the ministry submit the required equipment.

Field testing will be applied (for quality assurance), No equipment will be provided.

23. The Finished Quality of the turf (such as the level, slope and the evenness of the turf) depends highly on the sub-grade? Would the contract be liable if the installed turf has defects due to defects in the sub-grade work?

Inspection of the work (Installation will be done according to the scope of the work)

24. If the sub grade work is carried out by another party, will the contractor be given the option to conduct inspection during the sub grade work?

Contractor will be given option to inspect the sub base before Installation start.

25. Will preferred be given to contractors who propose to install FIFA preferred products instead of FIFA approved products?

The proposed will be evaluated and scored accordingly.

26. BDS does not mention any defects liability period It however mentioned there is no after-sale service can you confirm there will be no defects liability period?

Reference to the tender document and tender policy



Name: Aiminath Naheen Ahmed

Signature:

