




RAIN WATER HOLDING TANK & FOUNDATION PLAN



RAIN WATER HOLDING TANK & FOUNDATION-ELEVATION



- NOTES:-
1. ALL DIMENSIONS ARE IN MILLIMETRES AND ALL LEVELS AER IN METRES, UNLESS OTHERWISE NOTED.
  2. DRAWINGS ARE NOT TO BE SCALED. ONLY WRITTEN DIMENSIONS ARE TO BE FOLLOWED.
  3. ALL CONCRETE WORK SHALL BE DESIGN GRADE C30.
  4. BLINDING CONCRETE WORK SHALL BE GRADE C10.
  5. ALL STRUCTURE WORK SHALL CONFORM TO BS 7668. GRADE 46A/ASTMA36. ALL STRUCTURAL MEMBERS SHALL BE HOT DIP GALVANIZED AND PAINTED AS PER SPECIFICATIONS.
  6. STEEL BARS DENOTED "T" SHALL BE HYSD BARS OF GRADE 460 CONFIRMING TO BS 4449.
  7. NET SBC OF 15T/SQM IS CONSIDERED IN THE DESIGN.
  8. CLEAR COVER TO REINFORCEMENT
    - a. BEAM -40mm
    - b. SLAB -25mm



VIVEK V. PAGNIS  
(STRUCTURAL ENGINEER)

TENDER PURPOSE

CLIENT				MINISTRY OF ENVIRONMENT AND ENERGY MALDIVES REPUBLIC OF MALDIVES			
PROJECT				PROVISION OF RAINWATER HARVESTING SYSTEM IN 9 ISLANDS			
ASSIGNMENT				CONSULTANCY SERVICES FOR DESIGN AND SUPERVISION OF RAINWATER HARVESTING SYSTEM IN TH. VANDHOODHOO, TH. GAADHIFUSHI, TH. OMAADHOO, TH. KANDOODHOO, TH. KINBIDHOO, TH. DHYAMIGILI, M. RAYMANSDHOO, M. VEYVAH, M. NAALAFUSHI, MALDIVES (PACKAGE - 4)			
DRAWING TITLE				TYPICAL DRAWING OF RAW WATER STORAGE TANK TH.KANDOODHOO			
APPROVED	VVP	DRAWN	SSS	DESIGNED	SPP	CHECKED	PDP
SCALE	AS SHOWN	DATE	FEB 2018	DRAWING NUMBER	Th. Kandoodhoo/WS/08A	REVISION	0

CONSULTANT  
SHAH TECHNICAL CONSULTANTS PVT. LTD., INDIA  
IN ASSOCIATION WITH  
DEVELOPMENT TECHNOLOGIES MALDIVES, MALDIVES