

Ministry of Finance
Male', Republic of Maldives

Contractor Comments	Response/Reference Document
1. What is the condition of existing site? Are there any demolishing works or for cutting trees?	No Demolition work included
2. Can we get water and electricity for construction work under existing site condition?	Water supply and arrangement of electrical power to the site and for construction shall be Contractor's responsibility.
3. Is there any space for material storage?	Apart from Construction site, any additional temporary storages shall be arranged through Island authorities by Contractor.
4. Can we use Manufacture sand for the concrete work and other work like masonry and screeding etc...?	Recommend complying to technical specification.
5. Can we use local sand made blocks or equivalent for masonry work?	Usage of local sand are not recommended.
6. Do we need to include firefighting? Only fire extinguisher in BOQ. a. Only extinguisher or do you require additional fire system?	Extinguishers only
7. Do we need to include Air-conditioning? If yes, Please give details,	Air-conditioning system included in boq
8. Please give details for below connectivity,	Electricity: 60m feeder line to Panel connection Water: Connection to Utility supply Sewerage: Connection to Utility network
9. Is this duty free project?	Not applicable
10. Can you provide furniture details?	Provided in revised drawings
11. Can you provide solar panel specification?	Provided in revised boq
12. Can you provide the sizes (aluminum box and louvers sizes and thickness of these materials it has used in all the Grills?	Refer detailed drawings and technical specifications
13. Name board which materials you are suggesting for this board (Timber or Metals etc.)	12mm thick Acrylic plastic



14. Can you provide the thickness of Boundary wall?	Provided in revised drawings
15. How do you suggesting to fix Ramp Railing Are you suggesting to fix it in the screeding or to fix on the finishing materials?	Fix on screed / ground slab
16. Can you provide the details of materials it has used in Minaret to part for Aluminum Structure and Frame?	Apart from Aluminum, Concrete structure and exterior masonry shell wall complete with bracing beams.
17. Can you provide materials details it has used in Minaret Ladder and the gap distance in-between two steps?	Ladder shall be of stainless steel (grade 316) and other details can be derived from CAD files shared.
18. Can you provide the thickness and details for Rockwool?	50mm double side aluminum foil
19. In BOQ Ablution area doors has mentioned D4 and D5 but in the drawing there is no details for these two doors. Can you provide the details of these two doors?	Refer Architectural Drawings of “Ablution Area”
20. Can we request the location for Temporary accommodation and material storage?	Contractor to facilitate such accommodations through Island relevant authorities.
21. How about the water and Electricity facility availability at site?	Arrangement of electrical power to the site and for construction shall be Contractor’s responsibility.
22. Status of Harbor for Landing Craft.	Specifically arranged facility / provision not available at harbor
23. Is there any near spot to take electricity for work site (Stelco or Fenaka etc.)?	Utility distribution box is located around 200ft from site
24. Can we get water for construction work from site or can you provide the near location name and distance to get a water for site works or can we use island ground water for this project?	Water facility connection or ground well for immediate use not available at site. However, contractor may use ground water only where applicable.
25. Please mention the location for Disposal of Demolition and construction debris.	Island Waste Management Center

