



Ministry of Finance

Male', Republic of Maldives

Comments on Construction of Proposed 5 Classrooms and Staffroom (02 Storey) at HDh.Kurimbee School

CLARIFICATION 1

Contractor Comments	Response/Reference Document
1. Please mention the quantities of wall tiling and size of tiles?	300x600mm Quantities included in the revised BoQ
2. Please provide details of demolition and cutting of trees?	NO
3. Is EIA done for this project or do we need to make one by ourselves?	If previous EIA done, information to be given by School/MOE. Do not need make one for this project.
4. Where to dump construction debris?	5 MINS DRIVE TO WASTE DUMP AREA
5. Can we use local sand for Block making?	Can be used after proper cleaning but prefer river sand after proper cleaning.
6. Please clarify the availability of material storage and accommodation?	available
7. Can we use M-Sand for concrete?	For concrete manufacture sand can be used.
8. Can we use local sand for block work mortar and plastering?	Cannot use. Use river sand.
9. Can we use ground water for construction?	Cannot.
10. Where to get water and electricity?	A TEMPORARY CONNECTION FROM FENAKA FOR RENT
11. Please provide intended duration and budget of the project?	Contractor to submit
12. Rain water collection required or not?	required
13. Kindly provide the distance from the waste management site?	5 MINS DRIVE
14. Self levelling screeding mentioned in the drawings .it will be expensive than the normal screed, please conform?	To follow the drawing specs
15. Stiffener column reinforcement details not given?	2T12 & R6 @ 150 C/C
16. Kindly provide the distance from the Electrical main DB?	350FT FROM SITE

Je

