

بِسْمِ اللّٰهِ الرَّحْمٰنِ الرَّحِیْمِ



Ministry of Finance

Ameenee Magu, Male', Republic of Maldives

Telephone: (960) 334 9266, Fax: (960) 332 0706

މިނިސްޓްރީ ޕްރޮޕާޓީ ޖެޓިވްމަންޓް
މިނިސްޓްރީ ޕްރޮޕާޓީ ޖެޓިވްމަންޓް

CLARIFICATION 1

މަޢުލޫމާތު ޞަފްހާ 1

ނަންބަރު No:	TES/2019/W-076	
ފޮޓޯ ޖެޓިވްމަންޓް Project:	Construction of Proposed 03 Storey 12 Classrooms Building at Hdh.Atoll School (Hdh. Vaikaradhoo School)	
ދިނުމުގެ ދުވަސް Issued Date	23 rd July 2019	
ސަފްހާ ގެ އަދަދު No. of Pages: 02	ބީ.ޕީ. ގެ އަދަދު BoQ: -01	ޖެޓިވްމަންޓް ގެ އަދަދު Drawings: -00

Please include this amendment when submitting the bid. ބިދު ފޮޓޯ ޖެޓިވްމަންޓް ހުށަހަޅާ ފަދަ ވަރަށް ފުރުޞަތު ހޯދާނެ ގޮތަށް ބަލާށެވެ.

➤ Find the Responses to the Queries raised.

ނަންމު
Name: Ahmed Mujuthaba

ސަފްޞަފާ
Signature: 



Construction of Proposed 03 Storey 12 Classrooms Building at Hdh.Atoll School (Hdh.Vaikaradhoo School)

Contractor Comments	Response/Reference Document
1. Please provide site condition and demolition of any building or trees need to cut or transported	02 classrooms to be demolished .02 trees to be cut down
2. Ground water can be used for construction	Cannot be used
3. Please clarify the availability of material storage & accommodation	available
4. Is there any arrangement to dump construction debris? If so how far proposed location from the construction site	3 min drive
5. Please confirm whether temporary Electricity & water can be obtained from site	Available from school for rent
6. Please confirm manufactured rock sand can be used for structural Concrete works	Cannot be used
7. Can use local sand for Block making	Can be used after proper cleaning
8. Kindly provide the Distance from the Electrical Main DB	50ft
9. Kindly provide the Distance from the main sewer	100ft
10. Kindly provide the distance from the waste management site	5 min drive
11. Intended duration of the project and budget for project	220 days
12. Below ground level masonry and plastering item is not given in the BOQ	Included in ground floor columns
13. Stiffener column reinforcement details not given	2T12 & R6 @ 150 C/C
14. Below ground level masonry and plastering item is not given in the BOQ	Included in ground floor masonry and plastering
15. Staircase finishing - Titanium finishing is shown in the drawing, kindly confirm the staircase finishing. Item also not given in the BOQ	Included in BOQ under item: 9.4 600x600 anti slip homogeneous tiles followed drawing number A12 and A13. <i>Apologies for not adding the tiles on screed which was decided later on.</i>
16. Self levelling screeding mentioned in the drawing, it will be expensive than normal screed, please confirm	To follow the drawing specs
17. Rain water collection required or not	Required
18. Toilet wall tiles not included in the BOQ	Amended in attached BOQ item 9.6
19. Kindly provide Autocad drawing	Only PDF can be shared at this stage.


