



Ministry of Finance

Ameenee Magu, Male', Republic of Maldives

Telephone: (960) 334 9266, Fax: (960) 332 0706

މިނިސްޓްރީ އޮފް ފައިނަންސް
އަމީނީ މާގު ، ދުވަ ، ދިވެހިރާއްޖޭގެ ޖުމްހޫރިއްޔާ

CLARIFICATION 1

1 ވަނަ ބަޔާންކުރުމުގެ ސަބަބުން

| | | |
|--------------------------------------|---|---|
| ނަންބަރު No: | TES/2019/W-083 | |
| ފޮތްކުރާ ގޮތުގެ ނަންބަރު Project: | Construction of Proposed 04 Story 12 Classroom Building at HDh.Kulhudhufushi School (HDh.AEC) | |
| އުދުހުދުކުރާ ތާރީޚު Issued Date | 26 th August 2019 | |
| ސަފުހާގެ އަދަދު No. of Pages: -2 | ބޯޖު Boq: -00 | ޖަހާފައިވާ ވަނަވަންތަކުގެ އަދަދު Drawings: -00 |

މި ބަޔާންކުރުމުގެ ސަބަބުން ބަޔާންކުރާ ވަނަވަންތަކުގެ އަދަދު ބަދަލުވާނެއެވެ. ބަޔާންކުރާ ވަނަވަންތަކުގެ އަދަދު ބަދަލުވާނެއެވެ. ބަޔާންކުރާ ވަނަވަންތަކުގެ އަދަދު ބަދަލުވާނެއެވެ.

- Find attached clarification 1.

ނަންބަރު
Name: Fathimath Rishfa Ahmed

ސަފްދާ
Signature:





Ministry of Finance

Male', Republic of Maldives

TES/2019/W-83

Construction of Proposed 04 Story 12 Classroom Building at HDh.Kulhudhufushi School (HDh.AEC)

Clarification 01

| Contractor Comments | Response/Reference Document |
|---|---|
| 1. Please clarify the availability of material storage and accommodation with in the site premises? | YES |
| 2. Is there any arrangement to dump construction debris? If so how far proposed location from the construction site | 10 MIN DRIVE |
| 3. Is there any specific restriction or requirement on construction activity? | No demolition on concrete works on school hours |
| 4. Do we want to include Electrical main feeder cable? If yes, give us length? | Firstly, to check if required number of meters can be obtained from the existing panel board. IF NOT, length to be determined on site. |
| 5. Can we use manufacture sand for concrete and masonry work? | Yes. |
| 6. Can we use White sand for Block making? | Use local sand. |
| 7. Is there any major demolition works? | 2 CLASSROOMS AND 4 TOILET BLOCK |
| 8. Do we want to include Main Panel Board? If yes, please provide the location? | 40FT |
| 9. Please provide distance from existing sewerage network point to the building | 50FT |
| 10. Please provide distance from existing water network point to the building | 40FT AVAILABLE ON RENT |
| 11. Toilet wall tiles not included in the BoQ | Amended in the attached BOQ |
| 12. Please provide the reinforcement details of Column SC | 2T12 & R6 @ 150 C/C |
| 13. Waterproofing not included in the BOQ | Concrete waterproofing was included in the Bill 3.1.00 (i), and in the Bill 9.2 & 9.3 we had mentioned "sika product or equivalent" as waterproofing. |
| 14. Which document will be considered superior if there is any change between the drawings and the BOQ? | Drawings |
| 15.What kind of sand to be used for fabricating brick? | Local sand can be used after proper cleaning |
| 16.Are there any trees or Building on site? | 8 toilets, Toilet block to be demolished. |

