



۱

<p>No:</p>	<p>TES/2019/W-082</p>	
<p>Project:</p>	<p>Construction of proposed 02 Storey Multi-purpose Hall Building at S. Hithadhoo Addu High School</p>	
<p>Issued Date</p>	<p>18<sup>th</sup> August 2019</p>	
<p>No. of Pages: -2</p>	<p>Boq: -00</p>	<p>Drawings: -00</p>

Please include this amendment when submitting the bid.


- Find attached clarification 1.

سِرِّ

**Name: Fathimath Rishfa Ahmed**

$$x^2$$

**Signature:**





**Ministry of Finance**

Male', Republic of Maldives

**Construction of 02 Story Multipurpose School Hall Buildings at S.Hithadhoo, Addu  
High School  
TES/2019/W-82**

**Clarification 01**

Contractor Comments	Response/Reference Document
1. Details Required a) Capping beam Reinforcement details b) Glass thickness for the Doors and Windows c) Site Plan	Details are provided. All Tie Beams are FB1. 6mm Thickness Site information to be given by MOE
2. Do we want to include Electrical main feeder cable? If yes, give us length?	Firstly, to check if required number of meters can be obtained from the existing panel board. IF NOT, length to be determined on site.
3. Can we use manufacture sand for concrete and masonry work?	Yes.
4. Can we use White sand for Block making?	Use local sand.
5. Please clarify the availability of material storage with in site premises?	YES
6. Can you arrange space for staff accommodation?	YES
7. Kindly provide the site condition and detail of removal of trees	NO AND NO DEMOLITION
8. Do we want to include Main Panel Board? If yes, please provide the location?	YES
9. Please provide distance from existing sewerage network point to the building	5 MINUTES DRIVE
10. Please provide distance from existing water network point to the building	100FT , ON RENT AVAILABLE WATER AND ELECTRICITY CAN BE OBTAIN FROM SCHOOL ON RENT
11) Ref. Bill no. 3, Does not include Reinforcement and Foam Works.	Bill no 3.1.00 we have mentioned;  Rates shall include for: concrete, formwork, reinforcement, cleaning, fabrication, placing, the

AM

	provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage.
12) Ref. Bill no 15, Can we know the Size and length of Main Connection Cable. (Item no: 15.02.1).	Firstly, to check if required number of meters can be obtained from the existing panel board. IF NOT, length to be determined on site.
13) Ref. to drawing no.7, is CATWALK wall is a concrete wall or a masonry?	Please refer to the legend on floor plan. It is 150mm 1000mm High Solid Block Masonry Wall.
14) Ref. To drawing no. 7, does concrete is included for Parapet wall or is that a Masonry wall. Would appreciate some more details on this.	Please refer to the legend on floor plan. It is 150mm 1000mm High Solid Block Masonry Wall.

