



Ministry of Finance
 Ameenee Magu, Male', Republic of Maldives
 Telephone: (960) 334 9266, Fax: (960) 332 0706

މިނިސްޓްރީ ޕްރ ފޮނުވުމުގެ
 ސެކްޓަރުގެ ޖުމްހޫރިއްޔާ
 އިދާރާތަކުން

CLARIFICATION 2

2 ވަނަ ބަޔާންކުރުމުގެ ސަބަބުން

ނަންބަރު No:	TES/2019/W-09	
ފޮނުވާނެ ޕްރޮޖެކްޓް Project:	Construction of Major Roads at R.Ungoofaaru	
ފޮނުވާފައިވާ Issued Date	18 th March 2019	
ޕޭޖް ސަވަދީގެ އަދަދު No. of Pages: - 03	ބީޕީގެ އަދަދު Boq: - 00	ޑްރޯޕިންގ ޖެޓްޕްލާން Drawings: - 00

Please include this amendment when submitting the bid. ބަޔާންކުރުމުގެ ސަބަބުން ޕްރޮޖެކްޓް ޖެޓްޕްލާން ޕްރޮސެޖްޔާ ބެލެވޭ ބަޔާންކުރުމުގެ ސަބަބުން ޕްރޮޖެކްޓް ޖެޓްޕްލާން ޕްރޮސެޖްޔާ ބެލެވޭ

Below find clarifications for the queries which we have received.

- Need Details & quantities for installation of **Road Sign Boards**
Project Number :- TES/2019W-08-15
References- All Technical Specification – 1/a/i/6 (Permanent work)
Road Traffic Sign Boards are not included as part of the scope of works for this project.
- Need quantities or details (no. of intersections, etc..) for marking Zebra crossings at all Road intersections
Project Number :- TES/2019W-08-15
References- ALL BOQ - Road safety/Road marking
Road Traffic Sign Boards are not included as part of the scope of works of this project.
- Need quantities or details (no. of intersections, etc..) for construction of speed breakers at all Road intersections
Project Number :- TES/2019W-08-15
References- All BOQ - Road safety/Road marking
We have provided all the available drawings with the bid document. It is the responsibility of the contractor to prepare any additional drawings required.
- Need details for installation of PVC pipes (8", 6" & 4") – qnty. given (No. of pipes)
Project Number :- TES/2019W-08, 12, 13
References: BOQs – Gdh.Hanimaadhoo, S.Hulhumeedhoo & Th.Madifushi / Side walk/3.1.3 -3.15
8" will be used for interconnection of Settlement Tanks, 6" and 4" will be used as a provision for service lines.

5. Need boq item and quantity for filling soil & compaction for sub grade of Dhuvaafaru site
Project Number :- TES/2019W-11
Reference: Drawings (Road Concepts) – Dhuvaafaru
Refer to BoQ item 4.1.1.

6. Need boq item and quantity for Coral/rubble filling for green area of Dhuvaafaru site
Project Number :- TES/2019W-11
Reference: Drawings (Road Concepts) – Dhuvaafaru
Coral/Rubble filling for green area is not included as part of the scope of works of this project.

7. Layout for Road drainage and Cable junctions are not shown in concept of Roads
Project Number :- TES/2019W- 11
Reference: Drawings (Road Concepts) – Dhuvaafaru
Installation of Cable Junctions or Settlement Tanks are not included as part of the scope of works of this project.
For Storm Water Management System - Refer to Section IV Employer's Requirement, Scope of Works and Please refer to BoQ Item Number 1.3.2.

8. Layout for Road drainage (only one side shown) and Cable junctions are not shown in concept of Roads
Project Number :- TES/2019W- 15
Reference: Drawings (Road Concepts) – Gn.Fuvahmulah
Installation of Cable Junctions or Gutters are not included as part of the scope of works of this project.
For Storm Water Management System - Refer to Section IV Employer's Requirement, Scope of Works and Please refer to BoQ Item Number 1.3.2.

9. Need BOQ item, Quantity, Details of Retaining wall
Project Number :- TES/2019W-10
Reference :- Drawing (Road concept/ Type 08) – B.Eydafushi
Construction of Retaining wall is not included as part of the scope of works for this project.

10. Need concept types for Nooraanee Magu(S.No.#18) and Huravee Magu(S.No.#19) of B.Eydafushi Island
Project Number :- TES/2019W-10
Reference :- Drawing (Road concept) – B.Eydafushi/Concept of selected roads,
Standard Tender Document - B.Eydafushi - Scope of works, Page -62
For the Concept of Nooraanee Magu and Huravee Magu, Refer to Type 03 of Road Concept Drawings – B.Eydafushi.



11. Need concept type for School Magu(S.No.#12) of Hdh.Hanimaadhu Island

Project Number :- TES/2019W-08

Reference :- Drawing (Road concept) – Hdh.Hanimaadhu/Concept,
Standard Tender Document - Hdh.Hanimaadhu _Scope of works, Page -58

We have provided all the available drawings with the bid document. It is the responsibility of the contractor to prepare any additional drawings required.

For Length and Width of the road please refer to Standard Tender Document, Hdh.Hanimaadhoo – Scope of Works.

12. Layout for Cable junctions (only one side shown) is not shown in concept of Roads

Project Number :- TES/2019W- 08

Reference: Drawings (Road Concepts) – Hdh.Hanimaadhu/Road section Types -02, Type - 02A, Type -01B, Type-01,

Type – 02A – Cable junctions need to be installed on both sides

Type – 01B - Cable junctions need to be installed on both sides

Type – 01 - Cable junctions need to be installed on both sides

13. Mismatching details (widths) of Road & Side walk (see attachment CLARIFICATION DETAILS -02)

Project Number :- TES/2019W-08

Reference: Drawings (Road Concepts) – Hdh.Hanimaadhu/Road section Types
Standard Tender Document - Hdh.Hanimaadhu _Scope of works, Page -58

For Correct Road Length and Width of the roads please refer to Standard Tender Document, Hdh.Hanimaadhoo – Scope of Works.

ނަން

Name: Aishath Nadheema

අත්

Signature:



