



۲۰ خرمیروزه شمس ۲

No:	TES/2019/W-096	
Project:	Construction of L. Kalaidhoo School.	
Issued Date	02 nd September 2019	
No. of Pages: -01	Boq: -00	Drawings: -00

Please include this amendment when submitting the bid. ٢٠٢٤

Below find clarifications for the queries which we have received.

1. Please clarify the availability of material storage and Accommodation with in the site premises.

In each site, only material storage can be arranged.

2. Is there any arrangement to dump construction debris? If so how far proposed location from the construction site

Island Councils will provide dump construction debris facilities along with a fee.

3. Do we want to include Electrical main feeder cable? If yes, give us length?

Already at the mosque site there's a meter board.

4. Can we use manufacture sand for concrete and masonry work?

As requested in the clarification sheet, manufacture sand for concrete and masonry can be used.

5. Can we use White sand for Block making?

No, white sand can be used for block making

6. Is there any major demolition works?

No

- ### 7. Explain Difference in Drawing and BOQ

- a) Beams at Level 3
Drawing -200x350mm
BOQ - 200x400mm

- b) Timber Ridge Beam
Drawing - 50x200mm
BO - 75x200mm

- c) Timber purlins
Drawing - 50x50mm
BOQ - 50x35mm

In all of the elements under Question 07, it should be followed the **drawings** only

سِرِّ

Name: Aishath Nadheema

 $\frac{x}{2}$

Signature:

