

BILL OF QUANTITIES

**Proposed 12 Classroom at AA.Mathiveri School (03
Storey)**

CLIENT : MINISTRY OF EDUCATION, GOVERNEMNT OF MALDIVES

SUMMARY OF BILLS OF QUANTITIES

Proposed 12 Classroom at AA.Mathiveri School (03 Storey)

DESCRIPTION		AMOUNT	%
Bill №: 01 - PRELIMINARIES			
Bill №: 02 - EXCAVATION AND FILLING			
Bill №: 03 - INSITU CONCRETE WORKS			
Bill №: 04 - MASONRY			
Bill №: 05 - STRUCTURAL METAL WORKS			
Bill №: 06 - ROOFING			
Bill №: 07 - WINDOWS, SCREENS & LIGHTS			
Bill №: 08 - DOORS, SHUTTERS & HATCHES			
Bill №: 09 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS			
Bill №: 10 - SUSPENDED CEILING			
Bill №: 11 - PAINTING & DECORATIONS			
Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES			
Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES			
Bill №: 14 - PLUMBING			
Bill №: 15 - INSULATION, FIRE STOPPING & FIRE PROTECTION			
Bill №: 16 - ADDITIONS AND OMMISIONS			
TOTAL AMOUNT			

Proposed 12 Classroom at AA.Mathiveri School (03 Storey)
Male', Republic of Maldives

BILL OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
1.0.00	Bill №: 01 - PRELIMINARIES				
1.1.00	<u>GENERAL NOTES</u> Abbreviations m - metre nr - numbers m3 - cubic metres m2 - square metres m - linear metre t - tons inc. - including mm - millimetre SS - stainless steel GI - galvanized iron				
1.2.00	<u>SITE MANAGEMENT COSTS</u> Allow for all on and off site management cost including costs of foreman and assistants, temporary services, telephone, fax, hoardings & similar.	item	1.00		
1.3.00	<u>SIGN BOARD</u> Allow for sign board.	nr	1.00		
1.4.00	<u>CLEAN-UP</u> Allow for clean-up upon completion of works.	item	1.00		
1.5.00	<u>INSURANCE, BONDS, GUARANTEES AND WARRANTIES</u> Insurance as stated in the general conditions.	item	1.00		
1.6.00	TOTAL OF BILL №: 01 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
2.0.00	Bill №: 02 - EXCAVATION AND FILLING				
2.1.00	<u>GENERAL</u> (a) Rates shall include for: leveling, grading, trimming, compacting to faces of excavation, keep sides plumb, backfilling, consolidating, and disposing surplus soil.				
2.3.00	<u>SITE CLEARING</u>				
2.3.01	Clear the area of site from rubbish and vegetable matters, stumps, roots. Rates shall include for removal of trees and tree stumps and disposal of such materials	m ²	473.14		
2.4.00	<u>EXCAVATION</u> Excavation quantities are measured to the faces of concrete members. Rates shall include for all the additional excavation required to place the formwork. Rates shall include for backfilling.				
2.4.01	Excavation for Foundation pads	m ³	128.99		
2.4.02	Excavation for Foundation beams	m ³	31.58		
2.5.00	<u>FILLING</u> Rate shall include for: levelling, grading, trimming, compacting and similar				
2.5.01	Compacted earth filling under ground slab	m ²	377.79		
2.6.00	<u>DAMP-PROOF MEMBRANE</u> Rate shall include for: dressing around and sealing to all penetrations,laps and turnups.				
2.6.01	Polythene damp proof membrane (500 gauge)	m ²	377.79		
2.7.00	<u>DE-WATERING</u> De-watering the excavation until completion of concrete work as required				
2.7.01		item	1.00		
2.8.00	TOTAL OF BILL №: 02 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
3.0.00	Bill №: 03 - INSITU CONCRETE WORKS				
3.1.00	<u>GENERAL</u> (a) Rates shall include for: placing in position, making good after removal of formwork, mortar touch up to all concrete and casting in all required items; additional concrete required to conform to structural and excavated tolerances (b) Mix ratio for reinforced concrete shall be 1:2:3 and lean concrete shall be 1:2:6. (c) All structural concrete shall be GRADE M25 and lean concrete shall be GRADE M15 (d) Rates shall include for: concrete, formwork, reinforcement, cleaning, fabrication, placing, the provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage. (e) Rates shall include for: all necessary boarding, supports, erecting, framing, temporary cambering, cutting, perforations for reinforcing bars, bolts, straps, ties, hangers, pipes and removal of formwork. (f) Rates shall include for: cleaning, fabrication, placing the provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage. (g) All reinforcing bars shall be high strength bars. (h) Slab soffits to be finished fairfaced, use plasteciser and formwork with reducing agent. (i) All exposed & external concrete members shall be casted with Masterpel 777 or equivalent water proofing chemical. (j) Rate shall include for applying 2 coats of waterproofing chemical to substructure.(Below ground level)				
3.1.01	Allow for Concrete Testing.	item	1.00		
3.2.00	<u>MASS CONCRETE</u> Quantity is measured to the edges of concrete foundation members. Rates shall be inclusive for any additional concrete required to place the formwork.				
3.2.01	50 mm Lean Concrete (Foundations)	m ³	5.37		
3.3.00	<u>REINFORCED INSITU CONCRETE</u> <u>SUB-STRUCTURE</u> FOUNDATION PADS				
3.3.01	2500 x 2500 x 400mm Foundation pads, F1	m ³	5.00		
3.3.02	2300 x 2300 x 350mm Foundation pads, F2	m ³	5.55		
3.3.03	1800 x 1800 x 300mm Foundation pads, F3	m ³	10.69		
3.3.04	1500 x 1500 x 300mm Foundation pads, F4	m ³	8.10		
3.3.05	1300 x 1300 x 300mm Foundation pads, F5	m ³	2.03		
3.3.06	900 x 900 x 300mm Foundation pads, F6	m ³	2.92		
	FOUNDATION BEAMS				
3.3.07	450 x 200 mm Foundation beam, TB	m ³	20.51		
	STAIR STARTER				
3.3.08	200 x 1275 mm Concrete stair starter	m ³	0.54		
	COLUMNS				
3.3.09	225 x 400 mm Concrete columns C1	m ³	0.11		
3.3.10	225 x 400 mm Concrete columns C2	m ³	0.22		
3.3.11	200 x 300 mm Concrete columns C3	m ³	0.58		
3.3.12	200 x 200 mm Concrete columns C4	m ³	0.29		
3.3.13	200 x 300 mm Concrete columns C5	m ³	0.36		
3.4.00	<u>GROUND FLOOR</u> COLUMNS				
3.4.01	225 x 400 mm Concrete columns C1	m ³	0.50		
3.4.02	225 x 400 mm Concrete columns C2	m ³	1.01		
3.4.03	200 x 300 mm Concrete columns C3	m ³	2.69		
3.4.04	200 x 200 mm Concrete columns C4	m ³	1.34		
3.4.05	200 x 300 mm Concrete columns C5	m ³	1.68		
3.4.06	150 x 150 mm Concrete columns SC	m ³	0.47		
	SLABS				
3.4.07	100 mm thk Concrete Slab on ground	m ³	40.91		
3.4.08	100 mm thk Concrete Slab on ramp	m ³	0.57		
3.4.09	150 mm thk Concrete Slab on Half landing	m ³	2.01		
	STAIRCASE				
3.4.10	Concrete staircase GF to FFL	m ³	0.35		
3.4.12	Concrete staircase GF to 1st FL	m ³	3.77		

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL RATE	LABOUR RATE
	HALF LANDING BEAMS					
3.4.13	400 x	200 mm Beam B2	m ³	0.72		
3.4.14	400 x	200 mm Beam B3	m ³	0.41		
3.5.00	<u>FIRST FLOOR</u>					
	COLUMNS					
3.5.01	225 x	400 mm Concrete columns C1	m ³	0.50		
3.5.02	225 x	400 mm Concrete columns C2	m ³	1.01		
3.5.03	200 x	300 mm Concrete columns C3	m ³	2.69		
3.5.04	200 x	200 mm Concrete columns C4	m ³	1.34		
3.5.05	200 x	300 mm Concrete columns C5	m ³	1.68		
3.5.06	150 x	150 mm Concrete columns SC	m ³	0.47		
	SLABS					
3.5.07		180 mm thk Concrete Slab on first floor	m ³	41.54		
3.5.08		135 mm thk Concrete Slab on first floor	m ³	18.31		
3.5.09		150 mm thk Concrete Slab on Half landing	m ³	2.01		
	BEAMS					
3.5.10	475 x	200 mm Beam B1	m ³	2.38		
3.5.11	400 x	200 mm Beam B2	m ³	7.26		
3.5.12	400 x	200 mm Beam B3	m ³	2.76		
3.5.13	400 x	200 mm Beam B4	m ³	2.79		
3.5.14	180 x	400 mm Beam HB	m ³	1.86		
	HALF LANDING BEAMS					
3.5.15	400 x	200 mm Beam B2	m ³	0.72		
3.5.16	400 x	200 mm Beam B3	m ³	0.41		
	STAIRCASE					
3.5.17		Concrete staircase 1st to 2nd FL	m ³	1.82		
	RC WALL					
3.5.18		100mm thk 100mm high RC wall starter	m ³	0.35		
3.6.00	<u>SECOND FLOOR</u>					
	COLUMNS					
3.6.01	225 x	400 mm Concrete columns C1	m ³	0.50		
3.6.02	225 x	400 mm Concrete columns C2	m ³	1.01		
3.6.03	200 x	300 mm Concrete columns C3	m ³	2.69		
3.6.04	200 x	200 mm Concrete columns C4	m ³	1.34		
3.6.05	200 x	300 mm Concrete columns C5	m ³	1.68		
3.6.06	150 x	150 mm Concrete columns SC	m ³	0.47		
	SLABS					
3.6.07		180 mm thk Concrete Slab on Second floor	m ³	41.54		
3.6.08		135 mm thk Concrete Slab on Second floor	m ³	18.31		
	BEAMS					
3.6.09	475 x	200 mm Beam B1	m ³	2.38		
3.6.10	400 x	200 mm Beam B2	m ³	7.26		
3.6.11	400 x	200 mm Beam B3	m ³	2.79		
3.6.12	400 x	200 mm Beam B4	m ³	2.79		
3.6.13	180 x	400 mm Beam HB	m ³	1.86		
	RC WALL					
3.6.14		100mm thk 100mm high RC wall starter	m ³	0.35		
3.7.00	<u>ROOF LEVEL -01</u>					
	BEAMS					
3.7.01	300 x	200 mm Beam RB1	m ³	3.05		
3.8.00	<u>ROOF LEVEL -02</u>					
	BEAMS					
3.8.01	300 x	200 mm Beam RB1	m ³	8.26		
3.9.00	<u>OTHER WORKS</u>					
	Lintel and Sill beams					
3.9.01	150 x	150 mm Beam LT1	item	1.00		
3.9.02	300 x	150 mm Beam LT2	item	1.00		
	SHADING					
3.9.03		120 mm thk Concrete shading @ 1st slab level	item	1.00		
3.9.04		120 mm thk Concrete shading @ 2nd slab level	item	1.00		
3.9.05		120 mm thk Concrete shading @ roof beam level	item	1.00		
	FIN					
3.9.06	150 x	62 mm RC fin @ ground floor	item	1.00		
3.9.07	150 x	62 mm RC fin @ 1st floor	item	1.00		

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL RATE	LABOUR RATE
3.9.08	150 x	62 mm RC fin @ 2nd floor	item	1.00		
		RC bench				
3.9.09		75 mm thk Concrete Slab for vanity at toilet	item	1.00		
3.9.10		GROUND WELL				
		1000mm Dia Water well as per detailed drawing	item	1.00		
3.9.11		SEPTIC TANK DETAILS				
		150mm thk Concrete septic tank	item	1.00		
3.10.00		TOTAL OF BILL №: 03 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
4.0.00	Bill №: 04 - MASONRY				
4.1.00	<u>GENERAL</u> (a) Rates shall include for: cleaning out cavities, forming rebated reveals and pointing and cleaning down to reveals where necessary; fractional size blocks, all necessary machine cutting, cutting or forming chases or edges of floor slabs, cutting or leavingholes and openings as recesses for and building in pipes, conduits, sleeves and similar as required for all trades; leaving surfaces rough or raking out joints for plastering and flashing, bedding frames or plates, building in joists, bearers or similar, temporary supports to openings, templates, reinforcement in walls and for all necessary making good.				
4.2.00	<u>BLOCK WORK</u>				
4.2.01	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar (BELOW RAMP). 150 mm thk full height BELOW GROUND LEVEL	m ²	13.50		
4.2.02	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar. (EXTERNAL WALLS) 150 mm thk full height GROUND FLOOR	m ²	257.59		
4.2.03	FIRST FLOOR	m ²	187.69		
4.2.04	SECOND FLOOR	m ²	199.39		
4.2.05	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar (INTERNAL WALLS). 150 mm thk full height GROUND FLOOR	m ²	150.17		
4.2.06	FIRST FLOOR	m ²	104.14		
4.2.07	SECOND FLOOR	m ²	104.14		
4.2.08	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar (INTERNAL WALLS). 100 mm thk full height GROUND FLOOR	m ²	16.14		
4.2.09	FIRST FLOOR	m ²	18.34		
4.2.10	SECOND FLOOR	m ²	18.34		
4.2.11	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar (INTERNAL WALLS). 100 mm thk 2.4m height GROUND FLOOR	m ²	15.12		
4.2.12	FIRST FLOOR	m ²	29.76		
4.2.13	SECOND FLOOR	m ²	29.76		
4.2.14	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar (BELOW RAMP). 150 mm thk full height BELOW GROUND LEVEL	m ²	13.50		

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
4.3.00	TOTAL OF BILL №: 04 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
5.0.00	Bill №: 05 - STRUCTURAL METAL WORKS				
5.1.00	<p>GENERAL</p> <p>(a) Rates shall include for: all fabrication work, welding, marking, drilling for bolts incl. those securing timbers, steel plates, bolts, nuts and any type of washer, riveted work, counter sinking and tapping for bolts or machine screws.</p> <p>(b) Rates shall include for fabrication and erection and temporary supports and fixing into position.</p> <p>(c) “Welding” is deemed to be in accordance with the specification and for the material to which it is to be used. Gusset plates, shoe plates, ends, caps, cleats, brackets, stiffeners, bolts, etc.,are required to be included to the rate of the associated steel work in which they occur.</p> <p>(d) For the description of materials and workmanship refer to the Specification of works, pricing Preambles and Drawings.</p> <p>(e) Contractor shall submit shop drawings for approval prior to fabrication.</p> <p>(f) Unless specified otherwise, rate shall include for: All shop fabrication work, marking, delivery, unloading, hoisting, erecting and fixing as per detail drawings, All welds & allowance for rolling margin, the weight of weld metal in welded constructions, members of any length, cutting to size and shape and joints in the running length, grinding to a smooth finish, unless otherwise required, Machine drilled bolt, holes, bolts, nuts and washers, cleats, shoe and gusset plates and all other connections, Wire brushing to clean all the steel surfaces (except stainless steel) after fabrication and spray painting with two coats of quick drying metal primer zinc phosphate & two coats of matt anti corrosive paint with final paint, all necessary accessories and preparation and submission of Shop Drawings and As Built Drawings as specified.</p>				
5.2.00	<p>STEEL TRUSS</p> <p>TRUSS TR1</p> <p>5.2.01 Steel truss 11.55m span with 60.3mm dia x 3.2mm thick CHS pipe top and bottom chord and 42.4mm dia. x 2.0mm thick CHS pipe web members</p> <p>STEEL FRAMING</p> <p>5.2.02 60.3mm dia x 3.2mm thick GI bracing beam</p> <p>5.2.03 50 x 100 x 2.5mm 'C' Purlins at 900 c/c</p>	no	12.00		
		m	34.90		
		m	488.60		
5.3.00	TOTAL OF BILL №: 05 - Carried Over To Summary				

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL RATE	LABOUR RATE
6.0.00		Bill №: 06 - ROOFING				
6.1.00	<u>GENERAL</u> (a) Rates shall include for: fair edges, dressing over angel fillets, roof sealant, turning into grooves, all other labours, circular edges, nails, screws and other fixings and laps.					
6.2.00	<u>MAIN ROOF COVERING</u>					
6.2.01		Lysaght roofing sheet to specification	m²	427.18		
6.2.02		50mm mineral wool insulation with reflective layers on both installed as per suppliers specifications with recommended lap length and air gap tape. Rate shall include for BRC mesh over purlins to support insulation layer.	m²	427.18		
6.3.00	<u>CAPPING</u>					
6.3.01		Lysaght ridge cap as per roofing sheet suppliers assembly	m	35.50		
6.4.00	<u>GUTTER</u>					
6.4.01	200 x	200 mm Zinc gutter	m	69.80		
6.5.00	<u>DOWN PIPE</u>					
6.5.01		82 mm dia rain water pipe	item	1.00		
		50 mm dia rain water outlet	item	1.00		
6.6.00	<u>FASCIA</u>					
6.6.01	50 x	200 mm fascia board	m	71.00		
6.7.00		TOTAL OF BILL №: 06 - Carried Over To Summary				

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL RATE	LABOUR RATE
7.0.00	Bill №: 07 - WINDOWS, SCREENS & LIGHTS					
7.1.00	<u>GENERAL</u> (a) Rates shall include for locks, latches, closers, push plates, pull handles, bolts, kick plates, hinges and all door & window hardware. (b) Rates shall include for door frames, mullions, transoms, trims, glazing, tinting, timber panels, boardings, framing, lining, fastenings and all fixings. (c) Sizes are given overall outside dimensions of actual doors and windows. (d) Thickness and sizes of glass panels are shown on the Drawings and doors and windows schedule (e) Rates shall include for all painting as specified (f) Rates shall include all items specified in the door schedule and specification. (g) Frames and sashes to be 25-60 micron white powder coated aluminium other wise specified.					
7.2.00	<u>WINDOWS</u>					
	<u>GROUND FLOOR</u>					
7.2.01	1525 x	1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	8.00		
7.2.02	2450 x	1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	8.00		
7.2.03	650 x	785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	4.00		
7.2.04	3000 x	600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	9.00		
7.2.05	2975 x	600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00		
7.2.06	1875 x	600 V3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00		
7.2.06	2550 x	600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00		
	<u>FIRST FLOOR</u>					
7.2.07	1525 x	1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	8.00		
7.2.08	2450 x	1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	8.00		
7.2.09	650 x	785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00		
7.2.10	1200 x	1535 W4 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	1.00		
7.2.11	3000 x	600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	9.00		
7.2.12	2975 x	600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00		
7.2.13	1875 x	600 V3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00		
7.2.14	2550 x	600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00		
	<u>SECOND FLOOR</u>					
7.2.15	1525 x	1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	8.00		
7.2.16	2450 x	1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	8.00		
7.2.17	650 x	785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00		
7.2.18	1200 x	1535 W4 - Aluminium window with reflective glass panel on aluminium frame	nr	1.00		
7.2.19	3000 x	600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	9.00		
7.2.20	2975 x	600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00		
7.2.21	1875 x	600 V3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00		
7.2.22	2550 x	600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00		
7.3.00	TOTAL OF BILL №: 07 - Carried Over To Summary					

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL RATE	LABOUR RATE
8.0.00		Bill №: 08 - DOORS, SHUTTERS & HATCHES				
8.1.00	<u>GENERAL</u>	(a) Rates shall include for locks, latches, closers, push plates, pull handles, bolts, kick plates, hinges and all door & window hardware. (b) Rates shall include for door frames, mullions, transoms, trims, glazing, tinting, timber panels, boardings, framing, lining, fastenings and all fixings. (c) Sizes are given overall outside dimensions of actual doors and windows. (d) Thickness and sizes of glass panels are shown on the Drawings and doors and windows schedule. (e) Rates shall include for all painting as specified (f) Rates shall include all items specified in the door schedule and specification. (g) Frames and sashes to be 25-60 micron white powder coated aluminium other wise specified.				
8.2.00	<u>DOORS</u>					
	<u>GROUND FLOOR</u>					
8.2.01	1000 x	2300 D1 - Aluminium panel door on Aluminium frame with 6mm clear glass	nr	8.00		
8.2.02	1000 x	2300 D2 - Aluminium panel door on Aluminium frame with aluminium louvers	nr	3.00		
8.2.03	900 x	2200 D3 - PVC panel door on PVC frame	nr	2.00		
8.2.04	700 x	2000 D4 - PVC panel door on PVC frame	nr	3.00		
8.2.05	1000 x	2300 D5 - Aluminium panel door on Aluminium frame	nr	1.00		
	<u>FIRST FLOOR</u>					
8.2.06	1000 x	2300 D1 - Aluminium panel door on Aluminium frame with 6mm clear glass	nr	9.00		
8.2.07	1000 x	2300 D2 - Aluminium panel door on Aluminium frame with aluminium louvers	nr	2.00		
8.2.08	900 x	2300 D3 - PVC panel door on PVC frame	nr	2.00		
8.2.09	700 x	2100 D4 - PVC panel door on PVC frame	nr	6.00		
	<u>SECOND FLOOR</u>					
8.2.10	1000 x	2300 D1 - Aluminium panel door on Aluminium frame with 6mm clear glass	nr	9.00		
8.2.11	1000 x	2300 D2 - Aluminium panel door on Aluminium frame with aluminium louvers	nr	2.00		
8.2.12	900 x	2300 D3 - PVC panel door on PVC frame	nr	2.00		
8.2.13	700 x	2100 D4 - PVC panel door on PVC frame	nr	4.00		
8.3.00		TOTAL OF BILL №: 08 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
9.0.00	Bill №: 09 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS				
9.1.00	GENERAL (a) Rates shall include for: fixing, bedding, grouting, and pointing materials; making good around pipes, sanitary fixtures, and similar; cleaning down and polishing. (b) "Masterseal 588" or equivalent should be applied on top of screeds and walls upto 300mm in all toilets. (C) All external surface of masonry wall should be waterproofed with "Masterseal 588" or equivalent				
9.2.00	PLASTERING 20 mm thk cement plaster on external surface as specified on the drawing.				
9.2.01	GROUND FLOOR	m ²	257.59		
9.2.02	FIRST FLOOR	m ²	187.69		
9.2.03	SECOND FLOOR	m ²	199.39		
	16 mm thk cement plaster on internal surface as specified on the drawing				
9.2.04	GROUND FLOOR	m ²	619.49		
9.2.05	FIRST FLOOR	m ²	492.17		
9.2.06	SECOND FLOOR	m ²	503.87		
9.3.00	CEMENT SCREED 50 mm thk cement screed				
9.3.01	GROUND FLOOR	m ²	274.93		
9.3.02	FIRST FLOOR	m ²	269.27		
9.3.03	SECOND FLOOR	m ²	269.27		
	35 mm thk cement screed with 2.5mm self levelling screed				
9.3.01	GROUND FLOOR	m ²	88.29		
9.3.02	FIRST FLOOR	m ²	72.42		
9.3.03	SECOND FLOOR	m ²	72.42		
	25 mm thk cement screed				
9.3.01	GROUND FLOOR	m ²	30.42		
9.3.02	FIRST FLOOR	m ²	36.85		
9.3.03	SECOND FLOOR	m ²	36.85		
9.4.00	FLOOR TILING 600 x 600 mm Homogenous Non-slip tiles				
9.4.01	GROUND FLOOR	m ²	347.34		
9.4.02	FIRST FLOOR	m ²	341.68		
9.4.03	SECOND FLOOR	m ²	341.68		
	300 x 300 mm Homogenous Non-slip tiles				
9.4.04	GROUND FLOOR	m ²	30.42		
9.4.05	FIRST FLOOR	m ²	36.85		
9.4.06	SECOND FLOOR	m ²	36.85		
9.5.00	FLOOR PAINTING Epoxy floor paint				
9.5.01	GROUND FLOOR	m ²	6.41		
9.6.00	WALL TILING 300 x 600 mm Homogenous tiles				
9.6.01	GROUND FLOOR	m ²	77.82		
9.6.02	FIRST FLOOR	m ²	68.36		
9.6.03	SECOND FLOOR	m ²	68.36		
9.7.00	STEP TILING Ground floor to Store room Ground floor to first floor First floor to second floor	item item item	1.00 1.00 1.00		
9.8.00	SKIRTING 120-150 mm Homogenous tile skirting				
9.8.01	GROUND FLOOR	item	1.00		
9.8.02	FIRST FLOOR	item	1.00		
9.8.03	SECOND FLOOR	item	1.00		

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
9.7.00	TOTAL OF BILL №: 09 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
10.0.00	Bill №: 10 - SUSPENDED CEILING				
10.1.00	<u>GENERAL</u> (a) Rates shall include for: all labour in framing, notching and fitting around projections, pipes, light fittings, hatches, grilles and similar and complete with cleats, packers, wedges and similar and all nails and screws.				
10.2.00	<u>PLASTERBOARD CEILING</u>				
10.2.01	Fixed "Boral" or equivalent plasterboard ceiling system with timber framing SECOND FLOOR	m ²	221.99		
10.2.02	6mm thk Cement board ceiling on roof eave / gable ceiling / toilet area GROUND FLOOR	m ²	26.94		
10.2.03	FIRST FLOOR	m ²	32.48		
10.2.04	SECOND FLOOR	m ²	192.06		
10.3.00	TOTAL OF BILL №: 10 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
11.0.00	Bill №: 11 - PAINTING & DECORATIONS				
11.1.00	<u>GENERAL</u> (a) Rates shall include for: the provision, erection and removal of scaffolding, preparation, wall putty application, rubbing down between coats and similar work, the protection and/or masking floors, fittings and similar work, removing and replacing door & window furniture. (b) All painting work shall be carried in accordance with the Specifications.				
11.2.00	<u>WALL PAINTING</u>				
11.2.01	Weatherbound paint finish as specified (EXTERNAL SURFACES) GROUND FLOOR	m ²	305.41		
11.2.02	FIRST FLOOR	m ²	237.76		
11.2.03	SECOND FLOOR	m ²	226.59		
11.2.04	Emulsion paint finish including putty application on brick walls as specified (INTERNAL SURFACES) GROUND FLOOR	m ²	619.49		
11.2.05	FIRST FLOOR	m ²	492.17		
11.2.06	SECOND FLOOR	m ²	503.87		
11.3.00	<u>CEILING PAINTING</u>				
11.3.01	Selected paint finish including putty application on ceiling as specified (CEILING) GROUND FLOOR	m ²	26.94		
11.3.02	FIRST FLOOR	m ²	32.48	-	
11.3.03	SECOND FLOOR	m ²	192.06		
11.4.00	TOTAL OF BILL №: 11 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
12.0.00	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES				
12.1.00	<u>GENERAL</u> (a) Rates shall include for: all fabrication work, welding, marking, drilling for bolts incl. those securing timbers, steel plates, bolts, nuts and any type of washer, riveted work, counter sinking and tapping for bolts or machine screws. (b) Rates shall include for fabrication and erection and temporary supports and fixing into position.				
12.2.00	<u>RAMP RAILING</u>				
12.2.01	50mm dia (1.5-2mm thk) SS 304 handrail at 900mm height as per drawing Ramp railing (Entrance area)	m	9.80		
12.3.00	<u>STAIRCASE RAILING</u>				
12.3.01	25 & 50 mm dia GI powder coated handrail at 900mm height as per drawing GROUND - 1ST FLOOR	m	6.40		
12.3.02	1ST - 2ND FLOOR	m	6.40		
12.4.00	<u>WALKWAY RAILING</u>				
12.4.01	25 & 50 mm dia SS hollow pipe handrail at 1100mm height as per drawing FIRST FLOOR	m	34.50		
12.4.02	SECOND FLOOR	m	34.50		
12.4.00	TOTAL OF BILL №: 12 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
13.0.00	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES				
13.1.00	<p>GENERAL</p> <p>(a) Design, provide and install electrical network for the entire building complete in accordance to standards set by the local governing body STELCO/FENAKA</p> <p>(b) The following items and description and the drawings are given as a guidance as to the nature of the information required to be returned by the contractor. Should they not be appropriate the contractor should provide a similar BOQ using the Additions/Omissions sheets provided at the back of this BOQ.</p> <p>(c) The cost shall include for: screws, nails, bolts, nuts, standard cable fixing or supporting clips, brackets, straps, rivets, plugs and all incidental accessories.</p> <p>(d) Rate shall include for necessary chasings, trenching, conduits, cables, cable trays, fittings and clips, cutting holes and chases in brick work/ block work/ concrete work complete with all necessary accessories such as sockets, connections, cable glands and boxes, hardware clips, soldering and jointing materials etc., for proper installing and laying of cables.</p> <p>(e) Rates for electrical isolators, conduits, fittings, equipment and similar items shall include for: all fixings to various building surfaces.</p> <p>(f) A light fixture is measured as one point; switch end of wire is not included in the quantity.</p> <p>(g) A point wiring for power points is measured (regardless of 1 gang, 2 gang etc) as one point for each socket outlet; other end of wire is not included in the quantity.</p> <p>(h) All under ground cables directly buried in ground/run in trenches to be properly laid and covered with cable tiles/trench covers. Rate for under ground cables shall include for all necessary excavation, sand layers, concrete tiles, warning strips and back filling with approved quality earth properly compacted, hot dipped galvanized brackets for trenches, accessories, etc as applicable.</p> <p>(i) The contractors are requested to refer Conditions of Contract, Special Conditions of Contract, Drawings and Specification and other relevant documents related to this tender prior to pricing of the following items</p> <p>(j) The contractor shall provide a schedule of all builder's work in connection with details of such items as necessary, along with the tender.</p> <p>(k) Rates for materials/ plants/ equipments not approved for duty free facilities to be quoted on duty paid basis.</p> <p>(l) All equipments shall be guaranteed for a period of 12 months from the date of commissioning or date of practical completion of the project which ever later</p> <p>(m) The rate shall include for insurance during handling, rehandling, transport, storage until ready for installation, delivery of equipments up to the point of installation and until handing over.</p> <p>(n) The rates shall include for comprehensive maintenance during defects liability period of 12 months from the date of handing over</p> <p>(o) The tenderer shall submit the following information on the items/equipments quoted for together with the tender.</p> <ol style="list-style-type: none"> make model No. technical data country of manufacture delivery period lead time for manufacturing. port of shipping CIF value of each item in foreign currency. Optional items and their additional cost. (additional cost to be submitted separately) Schedule of items to be carried out by others connected to installation of generators/transformers/Electrical panels such as some builders work and electrical connection. Details of all special features schedule attached to specification. 				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
	<p>(p) Rate for all electrical panels shall include for supply and installation of all necessary MCCBs, MCBS, EFRs, ELCBs, auxiliary contacts, Voltmeters, ammeters, Digital analyser,kWh meters, indicator lamps, selector switches, copper bus bars, inter locks, aligning and grounding of the panel, inter connectors, internal wiring connections to switch gear,steel channels and necessary hardware fixing insulating materials,all in fully enclosed metal clad panels and distribution boards completed as shown in drawing. They shall comply with the specifications andI.E.E.regulations and be complete to working order to the approval of local authorities.</p> <p>(q) Rate shall include for supply, installation, maintaining, testing and commissioning of the system for power and lighting according to drawings and specifications to working order.</p> <p>(r) All materials, equipment wiring shall confirm to local codes, specifications, standards/latest I.E.E. regulations (BS 7671).</p>				
13.2.00	<u>MAIN DISTRIBUTION, SUB DISTRIBUTION AND DISTRIBUTION SYSTEM</u>				
	<p><u>Main Panel Board and Sub-Distribution Boards (DB)</u></p> <p>Distribution Panel for each floor as shown on the drawing, complete with all incoming and outgoing MCBs, RCCBs, etc any other item required to working order, wall mounted wall mount steel powder coated, IP44 encloser with neutral link, earth bar and required accessories, all complete as per the specifications & drawings.</p>				
13.2.01	Main Panel Board	nr	1.00		
	Distribution Boards	nr	12.00		
13.2.02	Internet switch board	nr	1.00		
	<p><u>MAIN / SUB CABLING</u></p> <p>All under ground cables directly buried in ground/ in the trenches as appilcable, to be laid properly and covered with cable tiles, protection tapes, etc for mechanical protection, PVC sleeves may use if required. Rate shall include for all necessary works/accessories such as excavation, sand layers, cable tiles, warning strips and back filling with approved quality earth,properly compacted, to the satisfication of the Engineer.</p> <p>All above ground cables shall be laid on cable tray/ trucnking /conduits as appilcable and covered by tray covers, etc. for mechanical protection. PVC sleeves may use if required. Rate shall include for all necessary works/ accessories such as galvernized brackets, supporting materials, fittings, nails, cable ties, earthing, etc, trays shall be of required sizes, GI powder coated, and shotted, to the satisfication of Engineer</p>				
	<u>CABLING UP TO MDB / IF THE EXISTING PANEL BOARD IS NOT SUFFICIENT TO CATER PROPOSED BUILDING</u>				
13.2.03	Feeder cable	item	1.00		
	Cabling from main Electrical source to DB	item	1.00		
	Cabling from main internet source to internet switch board	item	1.00		
13.2.04	Supply and installation of panel board with KWh meter	item	1.00		
	Wiring and connection to main panel board from main electrical network	item	1.00		
13.3.00	<u>GENERAL EARTHING</u>				
13.3.01	Allow for the total earthing system inclusive of the necessary cables from all the DBs	item	1.00		
13.4.00	<u>POINT WIRING AND FITTINGS</u>				
	Rate shall include for supply & installation of cable, conduits for point wiring in concealed installations including lights,switches, power outlet,data points,isolators, etc, all as specified in the drawing				
13.4.01	Supply and Installation of 2 x 1C 1.5mm2 PVC/PVC/Cu + 2.5mm2 PVC/Cu earth cable c/w uPVC conduit, junction boxes etc. for lights and switches point wiring	nr	420.00		
13.4.02	Supply and Installation of 2 x 1C 2.5mm2 PVC/PVC/Cu + 2.5mm2 PVC/Cu earth cable c/w uPVC conduit, junction boxes,ethernet cables, RJ45 Connectors, VGA cables etc. for the Socket outlets point wiring	nr	248.00		
13.5.00	<u>FIXTURES</u>				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
	Rate shall include supply and installation of following lighting fixtures, socket outlets as specified and detailed, fixed in position including all fixing accessories, supports and connect to power, under following conditions 1. All bathrooms, out door light fixtures shall be IP65 2. All switches & sockets shall be ABB or equivalent brand.				
	LIGHTS AND SWITCHES				
13.5.01	Outdoor wall light 40W (IP65)	nr	53.00		
13.5.02	Mirror light (7W LED light)	nr	11.00		
13.5.03	Recessed Down light 12W LED	nr	28.00		
13.5.04	Ceiling light 18W LED	nr	6.00		
13.5.05	2 x 4' tube light with weather proof opal casing	nr	8.00		
13.5.06	2 x 4' fluorescent light with opal casing	nr	100.00		
13.5.07	Ceiling fan (52" - 54")	nr	48.00		
13.5.08	Light switch (1 G)	nr	31.00		
13.5.09	Light switch (2 G)	nr	27.00		
13.5.10	Light switch (3 G)	nr	1.00		
13.5.11	Light switch (4 G)	nr	37.00		
13.5.12	Light switch (5 G)	nr	5.00		
13.5.13	Exhaust fan	nr	6.00		
13.5.14	Emergency Lights	nr	24.00		
13.5.15	Exit lights	nr	33.00		
	Flex outlet	nr	7.00		
	Exhaust	nr	1.00		
	SOCKETS/NETWORK OUTLETS				
13.5.16	13 A twin sockets	nr	122.00		
13.5.17	13 A sockets	nr	45.00		
13.5.18	Twin computer network outlet	nr	12.00		
13.5.19	Data points	nr	12.00		
13.5.20	HDMI,VGA & RAC AV Sockets	nr	12.00		
13.5.21	HDMI,VGA & RAC AV Twin Sockets	nr	12.00		
13.5.22	Speakers with volume controller and paging mic	nr	21.00		
13.5.23	Two gang TV/SAT socket outlet	nr	12.00		
13.6.00	TOTAL OF BILL №: 13 - Carried Over To Summary				

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL RATE	LABOUR RATE
14.0.00		Bill №: 14 - PLUMBING				
14.1.00	GENERAL					
	(a) Rates shall include for sockets, running joints, connectors, elbows, junctions, valves, reducers, expansion joints, backnuts and similar, incidental fitting, clips saddles, brackets, straps, hangers, screws, nails and fixing complete, including cutting and forming holes, excavating, laying pipes and backfilling trenches. (b) All pipe work and fittings shall be high pressure PVC. (c) Rates shall include for supply and fixing of all pipes. (d) All sanitary fixtures used shall be of superior quality and approved by the architect/consultant on submission of samples.					
14.2.00	WATER SUPPLY					
	Provide and fix UPVC high pressure pipes including piping, connections, fittings, valves, excavations, ducting, fixing with brackets and leak testing.					
	<u>INTERNAL PLUMBING - FRESH WATER SUPPLY PIPE</u>					
14.2.01		Note: Internal plumbing to all toilets including supply and laying of pipes.	item	1.00		
	<u>EXTERNAL PLUMBING</u>					
14.2.02		All pipe works under groundfloor screed/slab to be laid for Waste water, sewage, fresh water and well water connection.	item	1.00		
14.2.03		Waste water and sewage connection from all the toilets including the necessary catch pits and manholes as necessary. Rates shall include for supply and laying of pipes including clean-outs as necessary.	item	1.00		
14.2.04		Water connection to all toilets. Rate shall include for supply and laying of pipes.	item	1.00		
14.3.00	DISCHARGE WORK					
14.3.01		Provide and fix UPVC pipes including vent pipes, vent cowls, cleaning eye, connections, fittings, valves, excavations, ducting, fixing with brackets, connecting to existing sewer line and leak testing.	item	1.00		
14.4.00	FIXTURES					
	Complete installation, cleaning and testing of:					
14.4.01		Wash basin	nr	11.00		
14.4.02		Wash basin tap	nr	11.00		
14.4.03		Muslim shower with stop valve	nr	15.00		
14.4.04		Soap holder	nr	15.00		
14.4.05		Floor Drain	nr	10.00		
14.4.06		Floor Gully	nr	14.00		
14.4.07	510 x	1110 mm Face Mirror	nr	11.00		
14.4.08		Water Closet	nr	15.00		
14.4.09	1875 x	600 mm Counter top with tile finish	nr	5.00		
14.4.10	1000 x	600 mm Counter top with tile finish	nr	1.00		
14.4.11		Water booster pump	item	1.00		
14.4.12		Water dispenser	set	3.00		
	<u>DISABLED TOILET</u>					
14.4.13		Wash basin	nr	1.00		
14.4.14		Wash basin tap	nr	1.00		
14.4.15		Muslim shower with stop valve	nr	1.00		
14.4.16		Soap holder	nr	1.00		
14.4.17		Floor Gully	nr	1.00		
14.4.18	510 x	1110 mm Face Mirror	nr	1.00		
14.4.19		Water Closet	nr	1.00		
14.4.20		SS Railings as per detailed drawing	set	1.00		
14.5.00		TOTAL OF BILL №: 14 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
15.0.00	Bill №: 15 - INSULATION, FIRE STOPPING & FIRE PROTECTION				
15.1.00	<u>GENERAL</u> (a) Rates shall include for: screws, nails, bolts, nuts, standard cable fixing or supporting clips, brackets, straps, rivets, plugs and all incidental accessories (b) Rates for cable conduits, fittings, equipment and similar items shall include for: all fixings to various building surfaces (c) Rates shall include for all necessary electrical wiring and accessories required for completion (d) All items shall be supply and complete installation				
15.2.01	FIRE EXTINGUISHERS (Confirming to BS EN 3-10)				
15.2.01	Supply and installation of 2Kg CO2 Extinguishers	nr	4.00		
15.2.02	Supply and installation of 9 Lt. water Extinguishers.	nr	4.00		
15.4.00	TOTAL OF BILL №: 15 - Carried Over To Summary				

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL RATE	LABOUR RATE
16.0.00	Bill №: 16 - ADDITIONS AND OMMISIONS				
16.1.00	<u>ADDITIONS</u>				
16.1.01	Bill №: 01 - PRELIMINARIES				
16.1.02	Bill №: 02 - EXCAVATION AND FILLING				
16.1.03	Bill №: 03 - INSITU CONCRETE WORKS				
16.1.04	Bill №: 04 - MASONRY				
16.1.05	Bill №: 05 - STRUCTURAL METAL WORKS				
16.1.06	Bill №: 06 - ROOFING				
16.1.07	Bill №: 07 - WINDOWS, SCREENS & LIGHTS				
16.1.08	Bill №: 08 - DOORS, SHUTTERS & HATCHES				
16.1.09	Bill №: 09 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS				
16.1.10	Bill №: 10 - SUSPENDED CEILING				
16.1.11	Bill №: 11 - PAINTING & DECORATIONS				
16.1.12	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES				
16.1.13	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES				
16.1.14	Bill №: 14 - PLUMBING				
16.1.15	Bill №: 15 - INSULATION, FIRE STOPPING & FIRE PROTECTION				
	<u>TOTAL</u>				
16.2.00	<u>OMISSIONS</u>				
16.2.01	Bill №: 01 - PRELIMINARIES				
16.2.02	Bill №: 02 - EXCAVATION AND FILLING				
16.2.03	Bill №: 03 - INSITU CONCRETE WORKS				
16.2.04	Bill №: 04 - MASONRY				
16.2.05	Bill №: 05 - STRUCTURAL METAL WORKS				
16.2.06	Bill №: 06 - ROOFING				
16.2.07	Bill №: 07 - WINDOWS, SCREENS & LIGHTS				
16.2.08	Bill №: 08 - DOORS, SHUTTERS & HATCHES				
16.2.09	Bill №: 09 - FLOOR, WALL, CEILING, AND ROOF FINISHINGS				
16.2.10	Bill №: 10 - SUSPENDED CEILING				
16.2.11	Bill №: 11 - PAINTING & DECORATIONS				
16.2.12	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES				
16.2.13	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES				
16.2.14	Bill №: 14 - PLUMBING				
16.2.15	Bill №: 15 - INSULATION, FIRE STOPPING & FIRE PROTECTION				
	<u>TOTAL</u>				
16.3.00	TOTAL OF BILL №: 15 - Carried Over To Summary				