





ADDENDUM 1

އަޅާ ބަދަލު 1

ނަންބަރު No:	TES/2023/G-017	
ޕްރޮޖެކްޓްގެ ނަންބަރު Project:	Supply and Installation of New Servers and Procurement of 30 kva UPS for Server Room	
އުފުލާ ދުވަހު Issued Date	11 th December 2023	
ސަފުހާގެ އަދަދު No. of Pages: -03	ބޯޖުގެ އަދަދު Boq: -00	ނެޓްވર્ކްގެ އަދަދު Drawings: -00

Please include this addendum when submitting the bid. ބަދަލު 01 ގެ އަދަދު ބަލާފައިވާ ކަންކަމުގެ މަޢުލޫމާތު ބަލާލުމަށް ދަންނަވާނެއެވެ.

- Please find attached, Addendum 01 for the project.

ނަންބަރު Name: Aminath Naheen Ahmed	ސަފްދާ Signature:		
--	----------------------	--	---

ADDENDUM 01

This Addendum 01 is issued in accordance with Sub-Clause No. 8.1 of Section 1 – Instructions to Bidders. The addendum forms part of the Bidding Document.

Section 6: Schedule of Supply

3. Technical Specification

2) UPS

Replace as follows:

Requirements		Compliance (Yes / No)
Country of Origin: <i>(please specify)</i>		
Configured UPS capacity	30kVA (modular - upgradable to 60kVA)	
Type / Features:	<ul style="list-style-type: none">• Modular, hot-swappable• Modular UPS designed for small data centers• Must support online maintenance through hot swapping• Online dual-conversion• Compatible with 19" standard rack• Input:<ul style="list-style-type: none">○ 3 Phase○ Voltage: 380/400/415 Vac○ Frequency: 40-70Hz○ PF \geq0.9• Output:<ul style="list-style-type: none">○ 3 Phase○ Voltage: 380/400/415 Vac○ PF:1○ Frequency: 50/60Hz• Integrated touch screen LCD for information display and easier operation• Integrated with 3 Phase PDU, monitoring, UPS, and power distribution in a rack system.• Battery<ul style="list-style-type: none">○ Protection: over-current, overcharge, over-discharge, and short-circuit○ Standard 19" rack mountable○ Intelligent BMS system: reliable working, alarm reporting, and remote monitoring	



(Handwritten signature)

	<ul style="list-style-type: none"> ○ Should be rear wiring connections suitable for rack deployment ○ Lithium iron phosphate (LiFePO4) battery 	
Installation	<p>Installation and provisioning to be done by the vendor Any required civil work and electrical work shall be done by the vendor Documentation and user acceptance testing On the job training on system maintenance and administration</p>	
	<ul style="list-style-type: none"> • Supplier must include manufacturer authorization for the proposed product and services. • Supplier must be Manufacturer authorized distributor in Maldives (Documents must be provided). • Product catalog (with the proposed configurations must be submitted along with the bid) 	

