



## CLARIFICATION 1

1 ވަނަ ބަޔާން

ނަންބަރު No:	TES/2019/W-44	
ޕްރޮޖެކްޓް Project:	Design and Build of Harbour Upgrade in Sh.Feydhoo.	
ދިނުމުގެ Issued Date	25 <sup>th</sup> November 2019	
ސަފުހާގެ އަދަދު No. of Pages: -01	ބޯޕް Boq: -00	ޖަހާމަތް Drawings: -00

Please include this amendment when submitting the bid. ބަޔާން ދިނުމުގެ ފަދަ ފުރުޞަތު ހޯދާ ފަރާތްތަކުން މި ބަޔާނު ހިމަނާ ގޮތަށް ހުށަހަޅާން ޖެހޭނެއެވެ.

### 1. Do we have to break the existing quay wall?

Sand seeping is the major issue. Therefore once awarded a detailed joint inspection will be carried out. From this the exact condition of the quaywall will be determined. For bidding quote for "Bill Number 4 - Quaywall structure" as it is in the given BOQ. You can quote for demolition in "Bill No. 8 - Additions and Omissions". Once the joint inspection is done we will revise the BOQ if necessary.

### 2. What is the current quay wall constructed of and the current condition of it?

Existing quaywall is constructed using L blocks. Main issue is sand seeping.

### 3. What is the current breakwater constructed of and if its boulders, can we re-use any boulders from the existing breakwater?

Existing Breakwater is constructed with rock boulders. You can use the rocks. As this is a design and Build contract the **winning contractor** has to make sure (with calculations) that the rocks at the site are appropriate to be used in the breakwater/revetment.

### 4. Do we have to reclaim the area next to revetment?

That area should be backfilled.

ނަންބަރު

Name: Ahmed Mujuthaba

ސަފް

Signature:

