



Ministry of Finance
Male', Republic of Maldives

Contractor Comments	Response/Reference Document
Not given details about heat insulation sand witch for roof slab. What we should do about this heat insulation.	Since there is a false ceiling below the slab which creates an air cavity that acts as insulation. So additional insulation under the roof slab is not required.
In BOQ have mentioned about Vinyl flooring but not having much more details in drawings as well specification. Could we have much more details?	Refer to finishes schedule in drawing set (page A.2.05)
Water proofing for roof slab. In BOQ it has mentioned two coat of water proofing compounds. Can we know weather this compound is application type or membrane type.	It can be either application. Selection can be done by client or consultant during construction
Is there not any special requirements for X-Ray room and Radiology Room like Led Doors?	Revised drawing attached
Is it clear land or any Underground Structure to remove from site?	Two Tree Root part need to be removed
Can you provide the existing underground service drawings?	There is no Underground Service in Allocated Area
Please mention the location for disposal of demolition and construction debris.	In Harbour Area
Availability of Water and Electricity for construction purpose at site.	Water Will be Provided by HC Well, Electricity Need to be Taken from MWSC Temporary Service
Are you providing the temporary land for contractor accommodation, material storage and workshop? Please mention extend of the lands.	Contractor Need to look for this, Can Contact with Council for the Land, Also Health Centre Back Yard has Land of Around 210'x100' Feet area
Are you certifying payment to claim for the cost of "material on site"?	No
What is the order of priority of the documents when it comes to the clarifications? 01. Specification 02. Drawings 03. BOQ or please specified	Specification, Drawings & BOQ