

BILL OF QUANTITIES
CLASSROOM BLOCK at LH.OLHUVELIFUSHI

CLIENT : MINISTRY OF EDUCATION, GOVERNMENT OF MALDIVES

SUMMARY OF BILLS OF QUANTITIES
CLASSROOM BLOCK at LH.OLHUVELIFUSHI

DESCRIPTION	AMOUNT	%
Bill No: 01 - PRELIMINARIES		
Bill No: 02 - EXCAVATION AND FILLING		
Bill No: 03 - INSITU CONCRETE WORKS		
Bill No: 04 - MASONRY		
Bill No: 05 - STRUCTURAL METAL WORKS		
Bill No: 06 - ROOFING		
Bill No: 07 - WINDOWS, SCREENS & LIGHTS		
Bill No: 08 - DOORS, SHUTTERS & HATCHES		
Bill No: 09 - FLOOR, WALL FINISHINGS		
Bill No: 10 - SUSPENDED CEILING		
Bill No: 11 - PAINTING & DECORATIONS		
Bill No: 12 - STAIRS, WALKWAYS AND BALUSTRADES		
Bill No: 13 - MECHANICAL & ELECTRICAL SERVICES		
Bill No: 14 - PLUMBING		
Bill No: 15 - FIRE SYSTEM		
Bill No: 16- ADDITIONS AND OMMISIONS		
SUB-TOTAL		
GST 8%		
GRAND TOTAL		

PREAMBLE NOTES

1.1 Discrepancies

All participants in the Tender exercise are deemed to have read the Specifications and BOQ carefully in conjunction with all the Contract Drawings. Any discrepancies between these documents are to be brought to the attention of the Employer and clarified prior to the closing of the Tender. Should any said discrepancies be discovered at a later date, the decision of the Employer is final and any extra cost due to the contractor as a result of such discrepancies will NOT be entertained whatsoever. The Contractor shall, at all times, exercise with care and professional scrutiny to ensure that there are no discrepancies and/or divergence between Contract Drawings and specifications prior to execution of any portion of the Works on site. The Contractor shall immediately give the Employer a written notice specifying any such discrepancies or divergence should he discovered such issues and the Employer shall issue instructions in regard thereto. The Contractor should exercise due diligence in this matter as a failure and/or negligence in complying with the above stated requirements may result in extra costs. Any extra costs incurred in respect therefore shall be borne solely by the Contractor.

1.2 General Notes

1. The Bill of Quantities shall be read in conjunction with the Instruction to Bidders, General Conditions of Contract, Appendix to bid, Technical Specification and Tender Drawings.
2. The rates and prices tendered in the priced Bill of Quantities shall, except in so far as it is otherwise provided under the Contract, include all constructional plant, labour, supervision, materials, transportation, installation/erection, profit, together with all general risks, liabilities and obligations set out or implied in the Contract.
3. The Tenderer is deemed to have visited the site/s and fully acquainted himself as to the location of each of the items and works to be carried out and to all conditions which may affect the performance of the works, including but not limited to:
 - Access to each of the roads where solid waste transfer process will be carried out, and Access for the dump site.
 - Restrictions applicable to working in proposed area.
 - All safety regulations and employer site safety procedures.
4. A rate or price shall be entered against each item in the Bill of Quantities, whether quantities are stated or not. All quantities given herein shall be deemed to be estimated quantities of the work to be done. Tenderer shall check and verify the quantities before submitting the tender.
5. The whole cost of complying with the provisions of the Contract shall be included in the items provided in the priced Bill of Quantities, and where no items are provided but required for completion of contract works, the cost shall be deemed to be distributed among the rates and prices entered for the related item of work.
6. General directions and descriptions of work and materials are not necessarily repeated or summarized in the Bill of Quantities. The Bidder shall refer to relevant sections of the Contract Document to fully understand the item requirements before entering rates or prices against each item in the Bill of Quantities. No variation is allowed for the given scope of work.
- 7.. Measurement standard applied for calculation of quantities are according to NRM-2, RICS.

CLASSROOM BLOCK at LH.OLHUVELIFUSHI
Male', Republic of Maldives

BILL OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
1.0.00	Bill №: 01 - PRELIMINARIES					
1.1.00	<u>GENERAL NOTES</u> <u>Abbreviations</u> m - metre nr - numbers m3 - cubic metres m2 - square metres m - linear metre t - tons inc. - including mm - millimetre SS - stainless steel GI - galvanized iron					
1.2.00	<u>SITE MANAGEMENT COSTS</u> Allow for all on and off site management cost including costs of foreman and assistants, temporary services, telephone, fax, hoardings & similar.	item	1.00			
1.3.00	<u>SIGN BOARD</u> Allow for sign board.	nr	1.00			
1.4.00	<u>CLEAN-UP</u> Allow for clean-up upon completion of works.	item	1.00			
1.5.00	<u>INSURANCE, BONDS, GUARANTEES AND WARRANTIES</u> Insurance as stated in the general conditions.	item	1.00			
1.6.00	<u>SHOP DRAWINGS & AS BUILT DRAWINGS</u> Allow for Shop Drawings during the progress of the project and As-Built Drawings after the completion of the project as stated in the general conditions.	item	1.00			
1.7.00	<u>SAFETY ON SITE</u> Safety on site:- Providing and maintaining adequate safety measures on site for all workers and all authorized visitors on site and protecting adjoining properties and people against falling objects or other with regard to the construction works	item	1.00			
1.6.00	TOTAL OF BILL №: 01 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
2.0.00	Bill №: 02 - EXCAVATION AND FILLING					
2.1.00	<u>GENERAL</u>					
	(a) Rates shall include for: leveling, grading, trimming, compacting to faces of excavation, keep sides plumb, backfilling, consolidating, and disposing surplus soil.					
2.2.00	<u>SITE CLEARING</u>					
2.2.01	Clear the area of site from rubbish and vegetable matters, stumps, roots. Rates shall include for removal of trees and tree stumps	m ²	335.56			
2.3.00	<u>EXCAVATION</u>					
	Excavation quantities are measured to the faces of concrete members. Rates shall include for all the additional excavation required to place the formwork. Rates shall include for backfilling.					
2.3.01	Excavation for Foundation pads	m ³	116.45			
2.3.02	Excavation for Foundation beams	m ³	47.25			
2.4.00	<u>FILLING</u>					
	Rate shall include for: levelling, grading, trimming, compacting and similar					
2.4.01	Compacted earth filling under ground slab	m ²	335.56			
2.4.02	150mm thick coarse aggregate layer under foundation	m ²	335.56			
2.5.00	<u>DAMP-PROOF MEMBRANE</u>					
	Rate shall include for: dressing around and sealing to all penetrations.					
2.5.01	Bituminous waterproofing membrane	m ²	335.56			
2.6.00	<u>DE-WATERING</u>					
2.6.01	De-watering the excavation until completion of concrete work as required	item	1.00			
2.7.00	TOTAL OF BILL №: 02 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
3.0.00	Bill №: 03 - INSITU CONCRETE WORKS					
3.1.00	<u>GENERAL</u>					
	(a) Rates shall include for: placing in position, making good after removal of formwork, mortar touch up to all concrete and casting in all required items; additional concrete required to conform to structural and excavated tolerances (b) Mix ratio for reinforced concrete shall be 1:2:3 and lean concrete shall be 1:2:6. (c) All structural concrete shall be GRADE M25 and lean concrete shall be GRADE M15 (d) Rates shall include for: concrete, formwork, reinforcement, cleaning, fabrication, placing, the provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage. (e) Rates shall include for: all necessary boarding, supports, erecting, framing, temporary cambering, cutting, perforations for reinforcing bars, bolts, straps, ties, hangers, pipes and removal of formwork. (f) Rates shall include for: cleaning, fabrication, placing the provision for all necessary temporary fixings and supports including tie wires and chair supports, laps, distribution bars and wastage. (g) All reinforcing bars shall be high strength bars. (h) Slab soffits to be finished fairfaced, use plasteciser and formwork with reducing agent. (i) Waterproofing shall be added to all areas specified.					
3.1.01	Allow for Concrete Testing.	item	1.00			
3.2.00	<u>MASS CONCRETE</u>					
	Quantity is measured to the edges of concrete foundation members. Rates shall be inclusive for any additional concrete required to place the formwork.					
3.2.01	50 mm Lean Concrete (Foundations)	m ³	6.55			
3.2.02	100 mm Lean Concrete (below ramp wall)	m ³	0.39			
3.3.00	<u>REINFORCED INSITU CONCRETE</u>					
	<u>SUB-STRUCTURE</u>					
	FOUNDATION PADS					
3.3.01	2500 x 2500 x 400mm Foundation pads, F1	m ³	5.00			
3.3.02	2200 x 2200 x 350mm Foundation pads, F2	m ³	3.39			
3.3.03	1800 x 1800 x 300mm Foundation pads, F3	m ³	10.70			
3.3.04	1600 x 1600 x 300mm Foundation pads, F4	m ³	6.15			
3.3.05	1300 x 1300 x 300mm Foundation pads, F5	m ³	2.03			
3.3.06	900 x 900 x 300mm Foundation pads, F6	m ³	2.43			
	FOUNDATION BEAMS					
3.3.07	450 x 200 mm Foundation beam, TB	m ³	17.01			
	STAIR STARTER					
3.3.08	200 x 1252 mm Concrete stair starter	m ³	0.19			
3.3.09	200 x 1148 mm Concrete stair starter	m ³	0.23			
	COLUMNS					
3.3.10	225 x 400 mm Concrete columns C1	m ³	0.13			
3.3.11	225 x 400 mm Concrete columns C2	m ³	0.19			
3.3.12	200 x 300 mm Concrete columns C3	m ³	0.59			
3.3.13	200 x 200 mm Concrete columns C4	m ³	0.28			
3.3.14	200 x 300 mm Concrete columns C5	m ³	0.34			
3.3.15	150 x 150 mm Concrete columns SC	m ³	0.10			
3.4.00	<u>GROUND FLOOR</u>					
	COLUMNS					
3.4.01	225 x 400 mm Concrete columns C1	m ³	0.47			
3.4.02	225 x 400 mm Concrete columns C2	m ³	0.71			
3.4.03	200 x 300 mm Concrete columns C3	m ³	2.19			
3.4.04	200 x 200 mm Concrete columns C4	m ³	1.04			
3.4.05	200 x 300 mm Concrete columns C5	m ³	1.25			

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
3.4.06	150 x 150 mm Concrete columns SC	m ³	0.36			
	SLABS					
3.4.07	100 mm thk Concrete Slab on ground	m ³	33.02			
3.4.08	100 mm thk Concrete Slab on ramp	m ³	0.58			
3.4.09	150 mm thk Concrete Slab on half landing level	m ³	1.98			
	STAIRCASE					
3.4.10	Concrete staircase GF to FFL (below ground level)	m ³	0.35			
3.4.11	Concrete staircase GF to 1st FL	m ³	3.67			
	HALF LANDING BEAMS					
3.4.12	400 x 200 mm Beam B2	m ³	0.46			
3.4.13	400 x 200 mm Beam B3	m ³	0.29			
3.5.00	<u>FIRST FLOOR</u>					
	COLUMNS					
3.5.01	225 x 400 mm Concrete columns C1	m ³	0.46			
3.5.02	225 x 400 mm Concrete columns C2	m ³	0.69			
3.5.03	200 x 300 mm Concrete columns C3	m ³	2.15			
3.5.04	200 x 200 mm Concrete columns C4	m ³	1.02			
3.5.05	200 x 300 mm Concrete columns C5	m ³	1.23			
3.5.06	150 x 150 mm Concrete columns SC	m ³	0.35			
	SLABS					
3.5.07	180 mm thk Concrete Slab on first floor	m ³	30.89			
3.5.08	135 mm thk Concrete Slab on first floor	m ³	16.12			
3.5.09	150 mm thk Concrete Slab on half landing level	m ³	1.98			
	STAIRCASE					
3.5.10	Concrete staircase 1st to 2nd FL	m ³	3.67			
	HALF LANDING BEAMS					
3.5.11	400 x 200 mm Beam B2	m ³	0.46			
3.5.12	400 x 200 mm Beam B3	m ³	0.29			
	BEAMS					
3.5.13	475 x 200 mm Beam B1	m ³	1.71			
3.5.14	400 x 200 mm Beam B2	m ³	4.41			
3.5.15	400 x 200 mm Beam B3	m ³	1.16			
3.5.16	400 x 200 mm Beam B4	m ³	1.29			
	RC STARTER					
3.5.17	100 x 100 mm RC Starter	m ³	0.27			
3.6.00	<u>SECOND FLOOR</u>					
	COLUMNS					
3.6.01	225 x 400 mm Concrete columns C1	m ³	0.54			
3.6.02	225 x 400 mm Concrete columns C2	m ³	0.80			
3.6.03	200 x 300 mm Concrete columns C3	m ³	2.48			
3.6.04	200 x 200 mm Concrete columns C4	m ³	1.18			
3.6.05	200 x 300 mm Concrete columns C5	m ³	1.42			
3.6.06	150 x 150 mm Concrete columns SC	m ³	0.40			
	SLABS					
3.6.07	180 mm thk Concrete Slab on second floor	m ³	30.89			
3.6.08	135 mm thk Concrete Slab on second floor	m ³	16.12			
	BEAMS					
3.6.09	475 x 200 mm Beam B1	m ³	1.71			
3.6.10	400 x 200 mm Beam B2	m ³	4.41			
3.6.11	400 x 200 mm Beam B3	m ³	1.16			
3.6.12	400 x 200 mm Beam B4	m ³	1.29			
	RC STARTER					
3.6.13	100 x 100 mm RC Starter	m ³	0.27			
3.7.00	<u>ROOF LEVEL</u>					
	BEAMS					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
3.7.01	300 x 200 mm Beam RB	m ³	9.16			
3.8.00	<u>OTHER WORKS</u>					
	Lintel and Sill beams					
3.8.01	150 x 150 mm Beam LT1	item	1.00			
3.8.02	300 x 150 mm Beam LT2	item	1.00			
	SHADING					
3.8.03	120 mm thk Concrete shading @ ground	m ³	1.16			
3.8.04	120 mm thk Concrete shading @ 1st floor	m ³	1.15			
3.8.05	120 mm thk Concrete shading @ 2nd floor	m ³	1.42			
	FIN					
3.8.06	150 x 62 mm RC fin @ ground floor	m ³	2.60			
3.8.07	150 x 62 mm RC fin @ 1st floor	m ³	2.60			
3.8.08	150 x 62 mm RC fin @ 2nd floor	m ³	2.60			
	RC WALL					
3.8.09	120 mm thk Concrete side wall @ ground floor	m ³	0.48			
3.8.10	120 mm thk Concrete side wall @ 1st floor	m ³	0.48			
3.8.11	120 mm thk Concrete side wall @ 2nd floor	m ³	0.61			
	SEPTIC TANK					
3.8.12	150 mm thk Concrete septic tank	no	1.00			
	WATER WELL					
3.8.13	1000 mm dia. Ground well	no	1.00			
3.09.00	TOTAL OF BILL №: 03 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
4.0.00	Bill №: 04 - MASONRY					
4.1.00	<u>GENERAL</u> (a) Rates shall include for: cleaning out cavities, forming rebated reveals and pointing and cleaning down to reveals where necessary; fractional size blocks, all necessary machine cutting, cutting or forming chases or edges of floor slabs, cutting or leavingholes and openings as recesses for and building in pipes, conduits, sleeves and similar as required for all trades; leaving surfaces rough or raking out joints for plastering and flashing, bedding frames or plates, building in joists, bearers or similar, temporary supports to openings, templates, reinforcement in walls and for all necessary making good.					
4.2.00	<u>BLOCK WORK</u> Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar. (EXTERNAL WALLS) 150 mm thk full height					
4.2.01	BELOW GROUND	m ²	138.68			
4.2.02	GROUND FLOOR	m ²	151.33			
4.2.03	FIRST FLOOR	m ²	149.55			
4.2.04	SECOND FLOOR	m ²	179.22			
	Cement block wall, bricks laid to form alternate courses of headers and stretchers, laid on and inc. mortar (INTERNAL WALLS). 150 mm thk full height					
4.2.05	GROUND FLOOR	m ²	112.27			
4.2.06	FIRST FLOOR	m ²	93.03			
4.2.07	SECOND FLOOR	m ²	82.38			
	100 mm thk full height					
4.2.08	GROUND FLOOR	m ²	6.61			
4.2.09	FIRST FLOOR	m ²	5.10			
4.2.10	SECOND FLOOR	m ²	3.54			
	100 mm thk 2.4m height					
4.2.11	GROUND FLOOR	m ²	15.72			
4.2.12	FIRST FLOOR	m ²	30.96			
4.3.00	TOTAL OF BILL №: 04 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
5.0.00	Bill №: 05 - STRUCTURAL METAL WORKS					
5.1.00	<p><u>GENERAL</u></p> <p>(a) Rates shall include for: all fabrication work, welding, marking, drilling for bolts incl. those securing timbers, steel plates, bolts, nuts and any type of washer, riveted work, counter sinking and tapping for bolts or machine screws.</p> <p>(b) Rates shall include for fabrication and erection and temporary supports and fixing into position.</p> <p>(c) "Welding" is deemed to be in accordance with the specification and for the material to which it is to be used. Gusset plates, shoe plates, ends, caps, cleats, brackets, stiffeners, bolts, etc., are required to be included to the rate of the associated steel work in which they occur.</p> <p>(d) For the description of materials and workmanship refer to the Specification of works, pricing Preambles and Drawings.</p> <p>(e) Contractor shall submit shop drawings for approval prior to fabrication.</p> <p>(f) Unless specified otherwise, rate shall include for: All shop fabrication work, marking, delivery, unloading, hoisting, erecting and fixing as per detail drawings, All welds & allowance for rolling margin, the weight of weld metal in welded constructions, members of any length, cutting to size and shape and joints in the running length, grinding to a smooth finish, unless otherwise required, Machine drilled bolt, holes, bolts, nuts and washers, cleats, shoe and gusset plates and all other connections, Wire brushing to clean all the steel surfaces (except stainless steel) after fabrication and spray painting with two coats of quick drying metal primer zinc phosphate & two coats of matt anti corrosive paint with final paint, all necessary accessories and preparation and submission of Shop Drawings and As Built Drawings as specified.</p>					
5.2.00	<u>STEEL TRUSS</u>					
5.2.01	<p>TRUSS TRI</p> <p>Steel truss 11.525m span with 60.3mm dia x 3.2mm thick CHS pipe top and bottom chord and 42.4mm dia. x 2.0mm thick CHS pipe web members</p>	no	10.00			
5.2.02	<p>STEEL FRAMING</p> <p>60.3mm dia x 3.2mm thick GI bracing beam</p>	m	58.74			
5.2.03	50 x 100 x 2.5mm 'C' Purlins at 900 c/c	m	440.61			
5.3.00	TOTAL OF BILL №: 05 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
6.0.00	Bill №: 06 - ROOFING					
6.1.00	<u>GENERAL</u>					
	(a) Rates shall include for: fair edges, dressing over angel fillets, roof sealant, turning into grooves, all other labours, circular edges, nails, screws and other fixings and laps.					
6.2.00	<u>MAIN ROOF COVERING</u>					
6.2.01	Lysaght roofing sheet to specification	m²	359.86			
6.2.02	50mm mineral wool insulation with reflective layers on both installed as per suppliers specifications with recommended lap length and air gap tape. Rate shall include for BRC mesh over purlins to support insulation layer.	m²	359.86			
6.3.00	<u>CAPPING / FLASHING</u>					
6.3.01	Lysaght ridge cap as per roofing sheet suppliers assembly	m	29.43			
6.3.02	Lysaght flashing as per roofing sheet suppliers assembly	m	24.50			
6.4.00	<u>GUTTER</u>					
6.4.01	200 x 200 mm Zinc gutter	m	58.84			
6.5.00	<u>DOWN PIPE</u>					
6.5.01	82 mm dia rain water pipe	item	1.00			
6.5.02	82 mm dia rain water outlet	item	1.00			
6.5.03	50 mm dia rain water outlet	item	1.00			
6.6.00	<u>FASCIA</u>					
6.6.01	50 x 200 mm fascia board	item	58.84			
6.7.00	TOTAL OF BILL №: 06 - Carried Over To Summary					

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
7.0.00	Bill №: 07 - WINDOWS, SCREENS & LIGHTS						
7.1.00	GENERAL						
	(a) Rates shall include for locks, latches, closers, push plates, pull handles, bolts, kick plates, hinges and all door & window hardware. (b) Rates shall include for door frames, mullions, transoms, trims, glazing, tinting, timber panels, boardings, framing, lining, fastenings and all fixings. (c) Sizes are given overall outside dimensions of actual doors and windows. (d) Thickness and sizes of glass panels are shown on the Drawings and doors and windows schedule (e) Rates shall include for all painting as specified (f) Rates shall include all items specified in the door schedule and specification. (g) Frames and sashes to be 25-60 micron white powder coated aluminium other wise specified.						
7.2.00	WINDOWS						
	GROUND FLOOR						
7.2.01	1525 x	1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	6.00			
7.2.02	2450 x	1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	6.00			
7.2.03	650 x	785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	4.00			
7.2.04	3000 x	600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	7.00			
7.2.05	2975 x	600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
7.2.06	1875 x	600 V3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00			
7.2.07	2550 x	600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
	FIRST FLOOR						
7.2.08	1525 x	1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	6.00			
7.2.09	2450 x	1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	6.00			
7.2.10	650 x	785 W3 - Aluminium window with aluminium louvers on aluminium frame	nr	2.00			
7.2.11	1200 x	1535 W4 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	1.00			
7.2.12	3000 x	600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	7.00			
7.2.13	2975 x	600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
7.2.14	2550 x	600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
	SECOND FLOOR						
7.2.15	1525 x	1300 W1 - Aluminium sliding window with clear glass panel on aluminium frame	nr	8.00			
7.2.16	2450 x	1535 W2 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	8.00			
7.2.18	1200 x	1535 W4 - Aluminium side/top hung window with reflective glass panel on aluminium frame	nr	1.00			
7.2.19	3000 x	600 V1 - Aluminium window with aluminium louvers on aluminium frame	nr	7.00			
7.2.20	2975 x	600 V2 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
7.2.21	2550 x	600 V4 - Aluminium window with aluminium louvers on aluminium frame	nr	1.00			
7.3.00	TOTAL OF BILL №: 07 - Carried Over To Summary						

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
8.0.00	Bill №: 08 - DOORS, SHUTTERS & HATCHES						
8.1.00	<u>GENERAL</u> (a) Rates shall include for locks, latches, closers, push plates, pull handles, bolts, kick plates, hinges and all door & window hardware. (b) Rates shall include for door frames, mullions, transoms, trims, glazing, tinting, timber panels, boardings, framing, lining, fastenings and all fixings. (c) Sizes are given overall outside dimensions of actual doors and windows. (d) Thickness and sizes of glass panels are shown on the Drawings and doors and windows schedule. (e) Rates shall include for all painting as specified (f) Rates shall include all items specified in the door schedule and specification. (g) Frames and sashes to be 25-60 micron white powder coated aluminium other wise specified.						
8.2.00	<u>DOORS</u>						
	<u>GROUND FLOOR</u>						
8.2.01	1000 x	2300 D1 - Aluminium panel door on Aluminium frame (single swing)	nr	6.00			
8.2.02	1000 x	2300 D2 - Aluminium panel door on Aluminium frame (single swing)	nr	3.00			
8.2.03	900 x	2200 D3 - Aluminium door on Aluminium frame (single swing)	nr	2.00			
8.2.04	700 x	2000 D4 - Aluminium door on Aluminium frame (single swing)	nr	3.00			
8.2.05	1000 x	2300 D5 - Aluminium panel door on Aluminium frame (single swing)	nr	1.00			
	<u>FIRST FLOOR</u>						
8.2.06	1000 x	2300 D1 - Aluminium panel door on Aluminium frame (single swing)	nr	7.00			
8.2.07	1000 x	2300 D2 - Aluminium panel door on Aluminium frame (single swing)	nr	2.00			
8.2.08	900 x	2200 D3 - Aluminium door on Aluminium frame (single swing)	nr	2.00			
8.2.09	700 x	2000 D4 - Aluminium door on Aluminium frame (single swing)	nr	6.00			
	<u>SECOND FLOOR</u>						
8.2.10	1000 x	2300 D1 - Aluminium panel door on Aluminium frame (single swing)	nr	9.00			
8.3.00	TOTAL OF BILL №: 08 - Carried Over To Summary						

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
9.0.00	Bill №: 09 - FLOOR, WALL FINISHINGS					
9.1.00	<u>GENERAL</u>					
	(a) Rates shall include for: grooving, bedding, grouting, and pointing materials; making good around pipes, sanitary fixtures, and similar; cleaning down and polishing.					
	(b) "Masterseal 588" or equivalent should be applied on top of screeds and walls upto 300mm in all toilets.					
	(c) All external surface of masonry wall should be waterproofed with "Masterseal 588" or equivalent					
9.2.00	<u>PLASTERING</u>					
	20 mm thk cement plaster on external surface as specified on the drawing.					
9.2.01	BELOW GROUND FLOOR	m ²	277.36			
9.2.02	GROUND FLOOR	m ²	151.33			
9.2.03	FIRST FLOOR	m ²	149.55			
9.2.04	SECOND FLOOR	m ²	179.22			
	16 mm thk cement plaster on internal surface as specified on the drawing					
9.2.05	GROUND FLOOR	m ²	420.53			
9.2.06	FIRST FLOOR	m ²	407.73			
9.2.07	SECOND FLOOR	m ²	351.06			
9.3.00	<u>CEMENT SCREED</u>					
	50 mm thk cement screed					
9.3.01	GROUND FLOOR	m ²	205.06			
9.3.02	FIRST FLOOR	m ²	200.26			
9.3.03	SECOND FLOOR	m ²	234.00			
	25 mm thk cement screed waterproofed with masterpel 777 or equivalent					
9.3.04	GROUND FLOOR	m ²	94.88			
9.3.05	FIRST FLOOR	m ²	91.08			
9.3.06	SECOND FLOOR	m ²	58.60			
	35 mm thk cement screed with 2.5mm self levelling cement screed					
9.3.07	GROUND FLOOR	m ²	5.82			
9.4.00	<u>FLOOR TILING</u>					
	600 x 600 mm Homogenous Non-slip tiles					
9.4.01	GROUND FLOOR	m ²	272.38			
9.4.02	FIRST FLOOR	m ²	258.86			
9.4.03	SECOND FLOOR	m ²	292.60			
	300 x 300 mm Homogenous Non-slip tiles					
9.4.04	GROUND FLOOR	m ²	27.56			
9.4.05	FIRST FLOOR	m ²	32.48			
9.5.00	<u>WALL TILING</u>					
	300 x 600 mm Homogenous tiles					
9.5.01	GROUND FLOOR	m ²	108.96			
9.5.02	FIRST FLOOR	m ²	128.16			
9.6.00	<u>FLOOR PAINTING</u>					
	Epoxy floor paint					
9.6.01	GROUND FLOOR	m ²	5.82			
9.7.00	<u>SKIRTING</u>					
	120-150 mm high Homogenous tile skirting					
9.7.01	GROUND FLOOR	m	148.20			
9.7.02	FIRST FLOOR	m	137.90			
9.7.03	SECOND FLOOR	m	143.30			
9.8.00	<u>STEP TILES</u>					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
9.8.01	Ground floor to First floor	m ²	15.60			
9.8.02	First floor to Second floor	m ²	15.60			
9.8.00	TOTAL OF BILL №: 09 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
10.0.00	Bill №: 10 - SUSPENDED CEILING					
10.1.00	<u>GENERAL</u> (a) Rates shall include for: all labour in framing, notching and fitting around projections, pipes, light fittings, hatches, grilles and similar and complete with cleats, packers, wedges and similar and all nails and screws.					
10.2.00	<u>PLASTERBOARD CEILING</u>					
	Fixed "Boral" or equivalent plasterboard ceiling system with timber framing					
10.2.01	SECOND FLOOR	m ²	222.34			
	6mm thick Cement board ceiling on roof eave / gable ceiling / toilet area					
10.2.02	GROUND FLOOR	m ²	27.56			
10.2.03	FIRST FLOOR	m ²	32.48			
10.2.04	SECOND FLOOR	m ²	131.46			
10.3.00	TOTAL OF BILL №: 10 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
11.0.00	Bill №: 11 - PAINTING & DECORATIONS					
11.1.00	<u>GENERAL</u> (a) Rates shall include for: the provision, erection and removal of scaffolding, preparation, wall putty application, rubbing down between coats and similar work, the protection and/or masking floors, fittings and similar work, removing and replacing door & window furniture. (b) All painting work shall be carried in accordance with the Specifications.					
11.2.00	<u>WALL PAINTING</u>					
	Weatherbound paint finish as specified (EXTERNAL SURFACES)					
11.2.01	GROUND FLOOR	m ²	208.35			
11.2.02	FIRST FLOOR	m ²	228.62			
11.2.03	SECOND FLOOR	m ²	275.04			
	Emulsion paint finish including putty application on brick walls as specified (INTERNAL SURFACES)					
11.2.04	GROUND FLOOR	m ²	509.84			
11.2.05	FIRST FLOOR	m ²	497.04			
11.2.06	SECOND FLOOR	m ²	414.40			
11.3.00	<u>CEILING PAINTING</u>					
	Emulsion paint finish including putty application on ceiling as specified (CEMENT BOARD)					
11.3.01	GROUND FLOOR	m ²	27.56			
11.3.02	FIRST FLOOR	m ²	32.48			
11.3.03	SECOND FLOOR	m ²	353.80			
	Emulsion paint finish including putty application on ceiling as specified (SLAB SOFFIT)					
11.3.04	GROUND FLOOR	m ²	289.94			
11.3.05	FIRST FLOOR	m ²	285.02			
11.4.00	TOTAL OF BILL №: 11 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
12.0.00	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES					
12.1.00	<u>GENERAL</u> (a) Rates shall include for: all fabrication work, welding, marking, drilling for bolts incl. those securing timbers, steel plates, bolts, nuts and any type of washer, riveted work, counter sinking and tapping for bolts or machine screws. (b) Rates shall include for fabrication and erection and temporary supports and fixing into position.					
12.2.00	<u>RAMP RAILING</u> 50mm dia (1.5-2mm thk) SS 304 handrail at 900mm height as per drawing					
12.2.01	RAMP	m	6.20			
12.2.00	<u>STAIRCASE RAILING</u> 25 and 50mm dia GI handrail at 900mm height as per drawing					
12.2.01	GROUND - 1ST FLOOR	m	6.40			
12.2.02	1ST FLOOR - 2ND FLOOR	m	7.76			
12.3.00	<u>WALKWAY RAILING</u> 25- 50mm dia (1.5-2mm thk) GI handrail at 900mm height as per drawing					
12.3.01	FIRST FLOOR	m	26.95			
12.3.02	SECOND FLOOR	m	26.95			
12.4.00	TOTAL OF BILL №: 12 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
13.0.00	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES					
13.1.00	<u>GENERAL</u> <ul style="list-style-type: none"> (a) Design, provide and install electrical network for the entire building complete in accordance to standards set by the local governing body STELCO. (b) The following items and description and the drawings are given as a guidance as to the nature of the information required to be returned by the contractor. Should they not be appropriate the contractor should provide a similar BOQ using the Additions/Omissions sheets provided at the back of this BOQ. (c) The cost shall include for: screws, nails, bolts, nuts, standard cable fixing or supporting clips, brackets, straps, rivets, plugs and all incidental accessories. (d) Rate shall include for necessary chasings, trenching, conduits, cables, cable trays, fittings and clips, cutting holes and chases in brick work/ block work/ concrete work complete with all necessary accessories such as sockets, connections, cable glands and boxes, hardware clips, soldering and jointing materials etc., for proper installing and laying of cables. (e) Rates for electrical isolators, conduits, fittings, equipment and similar items shall include for: all fixings to various building surfaces. (f) A light fixture is measured as one point; switch end of wire is not included in the quantity. (g) A point wiring for power points is measured (regardless of 1 gang, 2 gang etc) as one point for each socket outlet; other end of wire is not included in the quantity. (h) All under ground cables directly buried in ground/run in trenches to be properly laid and covered with cable tiles/trench covers. Rate for under ground cables shall include for all necessary excavation, sand layers, concrete tiles, warning strips and back filling with approved quality earth properly compacted, hot dipped galvanized brackets for trenches, accessories, etc as applicable. (i) The contractors are requested to refer Conditions of Contract, Special Conditions of Contract, Drawings and Specification and other relevant documents related to this tender prior to pricing of the following items (j) The contractor shall provide a schedule of all builder's work in connection with details of such items as necessary, along with the tender. (k) Rates for materials/ plants/ equipments not approved for duty free facilities to be quoted on duty paid basis. (l) All equipments shall be guaranteed for a period of 12 months from the date of commissioning or date of practical completion of the project which ever later (m) The rate shall include for insurance during handling, rehandling, transport, storage until ready for installation, delivery of equipments up to the point of installation and until handing over. (n) The rates shall include for comprehensive maintenance during defects liability period of 12 months from the date of handing over (o) The tenderer shall submit the following information on the items/equipments quoted for together with the tender. <ul style="list-style-type: none"> a. make b. model No. c. technical data d. country of manufacture e. delivery period f. lead time for manufacturing. g. port of shipping h. CIF value of each item in foreign currency. j. Optional items and their additional cost. (additional cost to be submitted separately) k. Schedule of items to be carried out by others connected to installation of generators/transformers/Electrical panels such as some builders work and electrical connection. l. Details of all special features m. schedule attached to specification. 					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
	<p>(p) Rate for all electrical panels shall include for supply and installation of all necessary MCCBs, MCBs, EFRs, ELCBs, auxiliary contacts, Voltmeters, ammeters, Digital analyser,kWh meters, indicator lamps, selector switches, copper bus bars, inter locks, aligning and grounding of the panel, inter connectors, internal wiring connections to switch gear,steel channels and necessary hardware fixing insulating materials,all in fully enclosed metal clad panels and distribution boards completed as shown in drawing. They shall comply with the specifications and I.E.E.regulations and be complete to working order to the approval of local authorities.</p> <p>(q) Rate shall include for supply, installation, maintaining, testing and commissioning of the system for power and lighting according to drawings and specifications to working order.</p> <p>(r) All materials, equipment wiring shall confirm to local codes, specifications, standards/latest I.E.E. regulations (BS 7671).</p>					
13.2.00	<u>MAIN DISTRIBUTION, SUB DISTRIBUTION AND DISTRIBUTION SYSTEM</u>					
	<p><u>Main Panel Board and Sub-Distribution Boards (DB)</u></p> <p>Main Panel Board on Ground floor and sub-Distribution Boards on each floor as shown on the drawing, complete with all incoming and outgoing MCBs, RCCBs, etc any other item required to working order, wall mounted wall mount steel powder coated, IP44 encloser with neutral link, earth bar and required accessories, all complete as per the specifications & drawings.</p>					
13.2.01	Main Panel Board	nr	1.00			
13.2.02	Distribution Boards	nr	10.00			
13.2.03	Internet switch board	nr	1.00			
	<p><u>MAIN / SUB CABLING</u></p> <p>All under ground cables directly buried in ground/ in the trenches as applicable, to be laid properly and covered with cable tiles, protection tapes, etc for mechanical protection, PVC sleeves may use if required. Rate shall include for all necessary works/accessories such as excavation, sand layers, cable tiles, warning strips and back filling with approved quality earth,properly compacted, to the satisfaction of the Engineer.</p> <p>All above ground cables shall be laid on cable tray/ trucnking /conduits as applicable and covered by tray covers, etc. for mechanical protection. PVC sleeves may use if required. Rate shall include for all necessary works/ accessories such as galvernized brackets, supporting materials, fittings, nails, cable ties, earthing, etc, trays shall be of required sizes, GI powder coated, and shotted, to the satisfaction of Engineer</p>					
	<p><u>CABLING UP TO MDB</u></p> <p>Feeder cable</p>	item	1.00			
13.2.04	Feeder cable	item	1.00			
13.2.05	Cabling from main Electrical source to DB	item	1.00			
13.2.06	Cabling from main internet source to internet switch board	item	1.00			
13.3.00	<u>GENERAL EARTHING</u>					
13.3.01	Allow for the total earthing system inclusive of the necessary cables from all the DBs	item	1.00			
13.4.00	<u>POINT WIRING AND FITTINGS</u>					
	<p>Rate shall include for supply & installation of cable, conduits for point wiring in concealed installations including switches, power outlet, isolators, etc, all as specified</p>					
13.4.01	Supply and Installation of 2 x 1C 1.5mm ² PVC/PVC/Cu + 2.5mm ² PVC/Cu earth cable c/w uPVC conduit, junction boxes etc. for light point wiring	nr	328.00			
	<p>Supply and Installation of 2 x 1C 2.5mm² PVC/PVC/Cu + 2.5mm² PVC/Cu earth cable c/w uPVC conduit, junction boxes,ethernet cables, RJ45 Connectors, VGA cables etc. for the Socket outlets point wiring</p>					
13.4.02	13 A twin sockets	nr	101.00			
13.4.03	13 A power outlet	nr	34.00			
13.4.04	Exhaust socket / Flex outlet	nr	5.00			

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
13.5.00	<u>FIXTURES</u>					
	Rate shall include supply and installation of following lighting fixtures, socket outlets as specified and detailed, fixed in position including all fixing accessories, supports and connect to power, under following conditions					
	1. ICU/ETU/ HDU/ operation theater lights shall be clean room type light fixtures.					
	2. All bathrooms, out door light fixtures shall be IP65					
	3. All lamps/fittings shall be supplied by reputed manufacturer and relevent technical specification for each every fittings to be forwarded					
	4. All switches and sockets shall be ABB or equivalent brand.					
13.5.01	Mirror light (7W LED light)	nr	11.00			
13.5.02	LED Recessed Down light 12W	nr	28.00			
13.5.03	LED Ceiling light 18W	nr	6.00			
13.5.04	LED tube light with weather proof opal casing	nr	8.00			
13.5.05	40W (IP 65) outdoor wall light	nr	43.00			
13.5.06	LED tube light with opal casing	nr	89.00			
13.5.07	Emergency light	nr	19.00			
13.5.08	Ceiling fan (52" - 54")	nr	40.00			
13.5.09	Light switch (1 G)	nr	23.00			
13.5.10	Light switch (2 G)	nr	26.00			
13.5.11	Light switch (3 G)	nr	1.00			
13.5.12	Light switch (4 G)	nr	29.00			
13.5.13	Light switch (5 G)	nr	5.00			
13.5.14	Exhaust fan	nr	1.00			
13.6.00	<u>TELEPHONE/NETWORK POINTS</u>					
13.6.01	Two gang TV/SAT socket outlet	nr	10.00			
13.6.02	TWIN COMPUTER NETWORK OUTLET	nr	10.00			
13.6.03	Speakers	nr	17.00			
13.6.04	HDMI, VGA & RAC AV SOCKET	nr	10.00			
13.6.05	HDMI, VGA & RAC AV TWIN SOCKET	nr	10.00			
13.6.06	Internet switch board	nr	1.00			
13.6.07	DATA POINT	nr	10.00			
13.6.08	PAGING MIC	nr	1.00			
13.6.09	VOLUME CONTROLLER	nr	1.00			

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
13.6.00	TOTAL OF BILL №: 13 - Carried Over To Summary					

ITEM	DESCRIPTION		UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
14.0.00	Bill №: 14 - PLUMBING						
14.1.00	<u>GENERAL</u>						
	(a) Rates shall include for sockets, running joints, connectors, elbows, junctions, valves, reducers, expansion joints, backnuts and similar, incidental fitting, clips saddles, brackets, straps, hangers, screws, nails and fixing complete, including cutting and forming holes, excavating, laying pipes and backfilling trenches. (b) All pipe work and fittings shall be high pressure PVC. (c) Rates shall include for supply and fixing of all pipes. (d) All sanitary fixtures used shall be of superior quality and approved by the architect/consultant on submission of samples.						
14.2.00	<u>WATER SUPPLY</u>						
	Provide and fix UPVC high pressure pipes including piping, connections, fittings, valves, excavations, ducting, fixing with brackets and leak testing.						
	<u>INTERNAL PLUMBING - FRESH WATER SUPPLY PIPE</u>						
14.2.01	Note: Internal plumbing to all toilets and kitchen including supply and laying of pipes.		item	1.00			
	<u>EXTERNAL PLUMBING</u>						
14.2.02	Connection to proposed septic tank		item	1.00			
14.2.03	Connection to ground water well.		item	1.00			
14.2.04	All pipe works under groundfloor screed/slab to be laid for Waste water, sewage, fresh water and well water connection.		item	1.00			
14.2.05	Waste water and sewage connection from all the toilets and kitchen including the necessary catch pits and manholes as necessary. Rates shall include for supply and laying of pipes including clean-outs as necessary.		item	1.00			
14.2.06	Ground water connection to all toilets, kitchen and laundry. Rate shall include for supply and laying of pipes.		item	1.00			
14.2.07	Water pump		item	1.00			
14.3.00	<u>DISCHARGE WORK</u>						
14.3.01	Provide and fix UPVC pipes including vent pipes, vent cowls, cleaning eye, connections, fittings, valves, excavations, ducting, fixing with brackets, connecting to existitng sewer line and leak testing.		item	1.00			
14.3.02	Connection to the existing sewer pipe		item	1.00			
14.4.00	<u>FIXTURES</u>						
	Complete installation, cleaning and testing of:						
14.4.01	Wash basin		nr	7.00			
14.4.02	Wash basin tap		nr	7.00			
14.4.03	Muslim shower with stop valve		nr	9.00			
14.4.04	Soap holder		nr	9.00			
14.4.05	Floor Drain		nr	6.00			
14.4.06	Floor Gully		nr	8.00			
14.4.07	510 x 1118	Face Mirror	nr	7.00			
14.4.08	Water Closet		nr	9.00			
14.4.09	1863 x	600 Counter top with tile finish	nr	1.00			
14.4.10	1000 x	600 Counter top with tile finish	nr	1.00			
14.4.11	1875 x	600 Counter top with tile finish	nr	2.00			
14.4.12	Gate valve		nr	4.00			
	<u>DISABLED TOILET</u>						
14.4.13	Wash basin		nr	1.00			
14.4.14	Wash basin tap		nr	1.00			
14.4.15	Muslim shower with stop valve		nr	1.00			
14.4.16	Soap holder		nr	1.00			
14.4.17	Floor Gully		nr	1.00			
14.4.18	510 x 1118	Face Mirror	nr	1.00			
14.4.19	Water Closet		nr	1.00			
14.4.20	SS grab bar railings		set	1.00			
14.4.21	Gate valve		nr	1.00			

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
14.5.00	TOTAL OF BILL №: 14 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
15.0.00	Bill №: 15 - FIRE SYSTEM					
15.1.00	<u>GENERAL</u> (a) Rates shall include for: screws, nails, bolts, nuts, standard cable fixing or supporting clips, brackets, straps, rivets, plugs and all incidental accessories. (b) Rates for work in trench shall include for: excavation, maintaining faces of excavations, backfilling, compaction, appropriate cable covers, warning tape and disposal of surplus spoil. (c) Rates for cable conduits, fittings, equipment and similar items shall include for: all fixings to various building surfaces (d) Rates shall include for: sockets, running joints, connectors, elbows, junctions, reducers, expansion joints; backnuts and similar; incidental fittings, clips, saddles, brackets, straps, hangers, screws, nails and fixing complete, including cutting and forming holes; excavating, laying pipes and backfilling trenches. (e) All items shall be supply and complete installation.					
15.2.00	<u>FIRE ALARM AND FIRE FIGHTING SYSTEM</u>					
15.2.01	NOTE: All fire resistant cables shall be enclosed in PVC conduite 2Kg Portable Fire Extinguisher, (CO ₂)		5.00			
15.2.02	9Liter Portable Fire Extinguisher, (H ₂ O)		5.00			
15.2.03	Exit		27.00			
15.3.00	TOTAL OF BILL №: 15 - Carried Over To Summary					

ITEM	DESCRIPTION	UNIT	QTY	MATERIAL	LABOUR RATE	AMOUNT
16.0.00	Bill №: 16- ADDITIONS AND OMMISIONS					
16.1.00	<u>ADDITIONS</u>					
16.1.01	Bill №: 01 - PRELIMINARIES					
16.1.02	Bill №: 02 - EXCAVATION AND FILLING					
16.1.03	Bill №: 03 - INSITU CONCRETE WORKS					
16.1.04	Bill №: 04 - MASONRY					
16.1.05	Bill №: 05 - STRUCTURAL METAL WORKS					
16.1.06	Bill №: 06 - ROOFING					
16.1.07	Bill №: 07 - WINDOWS, SCREENS & LIGHTS					
16.1.08	Bill №: 08 - DOORS, SHUTTERS & HATCHES					
16.1.09	Bill №: 09 - FLOOR, WALL FINISHINGS					
16.1.10	Bill №: 10 - SUSPENDEd CEILING					
16.1.11	Bill №: 11 - PAINTING & DECORATIONS					
16.1.12	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES					
16.1.13	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES					
16.1.14	Bill №: 14 - PLUMBING					
16.1.15	Bill №: 15 - FIRE SYSTEM					
	<u>TOTAL</u>					
16.2.00	<u>OMISSIONS</u>					
16.2.01	Bill №: 01 - PRELIMINARIES					
16.2.02	Bill №: 02 - EXCAVATION AND FILLING					
16.2.03	Bill №: 03 - INSITU CONCRETE WORKS					
16.2.04	Bill №: 04 - MASONRY					
16.2.05	Bill №: 05 - STRUCTURAL METAL WORKS					
16.2.06	Bill №: 06 - ROOFING					
16.2.07	Bill №: 07 - WINDOWS, SCREENS & LIGHTS					
16.2.08	Bill №: 08 - DOORS, SHUTTERS & HATCHES					
16.2.09	Bill №: 09 - FLOOR, WALL FINISHINGS					
16.2.10	Bill №: 10 - SUSPENDEd CEILING					
16.2.11	Bill №: 11 - PAINTING & DECORATIONS					
16.2.12	Bill №: 12 - STAIRS, WALKWAYS AND BALUSTRADES					
16.2.13	Bill №: 13 - MECHANICAL & ELECTRICAL SERVICES					
16.2.14	Bill №: 14 - PLUMBING					
16.2.15	Bill №: 15 - FIRE SYSTEM					
	<u>TOTAL</u>					
16.3.00	TOTAL OF BILL №: 16 - Carried Over To Summary					