

نَحْنُ خَيْرٌ مِّنْكَ ۖ شَوْ۟سِرٌۭ

No:	TES/2019/W-097	
Project:	Construction of proposed 02 Storey Multi-purpose Hall Building at Gdh.Atoll School (Gdh.Gahdhoo School)	
Issued Date	19 <sup>th</sup> August 2019	
No. of Pages: 02	BoQ: -00	Drawings: -01

Please include this amendment when submitting the bid. 10

- **Find the Responses to the Queries raised.**

**Signature:**



**Construction of Proposed 02 Storey Multi-Purpose Hall Building at Gdh.Atoll School (Gdh.Gandhoo)**

<b>Contractor Comments</b>	<b>Response/Reference Document</b>
1. Glass thickness for the Doors and Windows	6mm thick glass
2. Site Plan -	Attached
3. Do we want to include Electrical main feeder cable? If yes, give us length	150ft
4. Can we use manufacture sand for concrete and masonry work?	Manufactures sand can be used For Concrete and masonry plaster work. But for block work it cannot be used.
5. Can we use White sand for Block making ?	Technically, the white sand / local sand has more chloride / Sulphate content which will have negative impact on the strength parameter of the block. It is advisable to use white sand if no other alternate is available. Also washing of the white sand with clean potable water will reduce the chloride/Sulphate content considerably.
6. Please clarify the availability of material storage with in site premises	Yes
7. Can you arrange space for staff accommodation?	Yes
8. Kindly provide the site condition and detail of removal of trees	No demolition
9. Do we want to include Main Panel Board? If yes, please provide the location?	150ft
10. Please provide distance from existing sewerage network point to the building	300ft
11. Please provide distance from existing water network point to the building	300ft available for rent.

