



Ministry of Finance
Ameenee Magu, Male', Republic of Maldives
Telephone: 1617,(960) 334 9296

ދިވެހިސަރުކާރުގެ ގެޒެޓް އިން ބަޔާންކުރި ޖަހާލުމުގެ ދަށުން
އިދާރާތަކުން ބޭނުންކުރާ ޖަހާލުމުގެ ދަށުން

ސަފުޙާ 1

CLARIFICATION 1

ނަންބަރު No:	TES/2021/W-084		
ޕްރޮޖެކްޓް Project:	Construction of Fuvahmulah City (Dhoodigan) Mosque		
ޕްރޮޖެކްޓް ޖަހާލުމުގެ ދަތުރު Issued Date	August 4, 2021		
ސަފުޙާ ގެ އަދަދު No. of Pages: -01	ބޮޑުވަވަތް Boq: -00	ޖަހާލުމުގެ ދަތުރު Drawings: -00	

Please include this clarification when submitting the bid. ފަސޭހަކުރާ ގޮތުގައި ސަފުޙާ 1 ގައި ބަޔާންކުރި ޖަހާލުމުގެ ދަށުން ބޭނުންކުރާ ޖަހާލުމުގެ ދަށުން

- **Answers to the Queries are attached with this Clarification**

ނަންބަރު Name: Fathimath Rishfa Ahmed	ސަފުޙާ Signature:
---	-----------------------------



Ministry of Finance

Project Name: Construction of Fuvahmulah City (Dhoodigan) Mosque.

Project Number: TES/2021/W-084

Clarification 1

Question	Answers
1. SS pipe railing for ground floor stairs?	SS pipe railing for ground floor stairs
2. Door Schedule?	Temporary sites will be provided for all construction related purposes
3. Window Schedule (Only available W3 & W4 Details)	W1 and W2 included in AR19 D&W Schedule 01
4. Arch Pattern 3 Details?	as provided in AR05 Elevations E1 E2 main entrance
5. False canopy for rainwater discharge down pipe?	downpipes only connected to roof gutters. False canopies are only used above arches and do not require discharge downpipes
6. Sound Cupboard	contractor may propose flatpack cupboard for sound room
7. Masjid Name Board?	to be placed on wall above front arch
8. Calligraphy Board 2m x 4m	Wood embossed or engraved board in Mihrab Area
9. Calligraphy Board 1.5m x 4m?	Wood embossed or engraved board in Prayer area
10. Minaret GI Ladder?	contractor may propose to supply pre-fab ladders or fabricate bolted or welded GI
11. Minaret GI Ladder	pipes on site. Should have safe load bearing for 150kg.
12. Prefabricated Dome for Minaret	please omit 5.3 (1) as there should not be a pre-fabricated dome for minaret.
13. Minaret Door Schedule	door incorrectly labelled as D1 in AR09 Minaret Details1. It should be D5 as provided in AR19 D&W Schedule 01. D5 is 2150 x 700mm
Minaret MEP drawing	included in LT01 Lighting Layout and PO01 Power Layout
Items not included in the BOQ 1 : PA system - 2 : Boundary Wall - add following:	included in 12.5 Minaret BOQ add following: 16.2.5.1 Prefab wall panels as shown in drawings and renders 16.2.5.2 Exterior plastering 16.2.5.3 Exterior textured paint
Pavement Floor	58sqm paving area (800L x 400W x 300Dmm blocks) near front entrance and 2x 11sqm areas (400mm side hexagonal blocks x 300mm thick) near minaret.
Planter Box	half walls and planters 450mm height
Landscape	contractors to include provision for landscaping - add following: 16.2.6.1 Landscaping

Please clarify the Arch materials?	Arches should be made of concrete.
Please provide Canopy details. There are no details in the available drawing	only canopy above arches as provided in AR22 Arc Details 2
Please provide Solar panel Installation method and Connection Layout.	- only canopy above arches as provided in AR22 Arc Details 2
Please provide Solar panel Installation method and Connection Layout	Contractors should provide supplier drawings and specifications for consultant's approval.
Do we need to include Exterior Decorative elements for Prayer hall and Minaret? If needed please provide the details drawing with materials spec?	Please refer to drawings and renders provided.
What is the brand we want to consider for Main panel board, Distribution Board & Breakers	As stated in the specifications electrical fittings should be ABB or equivalent grade.
Please clarify the availability of material storage with in site premises.	Only Material storage space can be arranged within the site or nearby site.
Can we use manufacture sand for concrete and masonry work?	It should be river sand and aggregate for all works
Can we use White sand for Block making?	It should be river sand and aggregate for all works