


Uttheemu - Roof Top Details			
Sr No		Community Centre	Area (Ha)
1	RT-1	Council Office	0.0183
2	RT-2	Womens Mosque	0.0130
A		Hall -1	0.0018
B		Hall -2	0.0157
		Total	0.0157
3	RT-3	Bodu Thakurufan Memorial Centre	
A		Hall -1	0.0238
B		Hall -2	0.0859
C		Hall -3	0.0432
D		Hall -4	0.0130
E		Hall -5	0.0953
F		Hall -6	0.0169
G		Hall -7	0.0064
I		Hall -8	0.0036
		Total	0.2290
4	RT-4	Bandaarainge Mosque 1	
A		Hall -1	0.0759
B		Hall -2	0.0056
		Total	0.0815
5	RT-5	Health Centre	0.0240
6	RT-6	School	
A		Hall -1	0.0499
B		Hall -2	0.0064
C		Hall -3	0.0295
D		Hall -4 (G+2)	0.0170
E		Hall -5	0.0022
		Total	0.1049
7	RT-7	Court	0.0097
8	RT-8	Pre-School	0.0350
9	RT-9	Womens Mosque 2	0.0093
Grand Total Roof Area			0.5275


NOTES:

1. ALL COORDINATES ARE BASED ON WGS 84 DATUM UTM SYSTEM.
2. UTM GRID ZONE - 43 N
3. ALL LEVELS ARE IN METERS UNLESS OTHERWISE SPECIFIED.

LEGEND:-	
CONVEYANCE SYSTEM	
SLUICE VALVE	
WTP	
CATCHMENT ROOF	



REVISION				
No.	DESCRIPTION	BY	DATE	APPR.
CONSULTANT				
IN ASSOCIATION WITH				
SHAH TECHNICAL CONSULTANTS PVT. LTD., INDIA				
DEVELOPMENT TECHNOLOGIES MALDIVES, MALDIVES				

		MINISTRY OF ENVIRONMENT AND ENERGY	
		MALE' REPUBLIC OF MALDIVES	
PROJECT		PROVISION OF RAINWATER HARVESTING SYSTEM IN 10 ISLANDS	
ASSIGNMENT		CONSULTANCY SERVICES FOR DESIGN AND SUPERVISION OF RAINWATER HARVESTING SYSTEM IN HA. UTHEEMU, HA. MULHADHOO, HA. MURADHOO, HA. ULIGAMU, HA. MAARANDHOO, HA. FILLADHOO, HDH. FINEY, HDH. KURINBI, HDH. NEYKURENDHOO, HDH. HIRMARADHOO, MALDIVES [PACKAGE -1]	
DRAWING TITLE			
PROPOSED CONVEYANCE SYSTEM AND SUPPLY SYSTEM			
HA. UTHEEM			
APPROVED	CHECKED	DESIGNED	DRAWN
SSS	SSS	SPP	SSN
SCALE	DATE	DRAWING NUMBER	REVISION
1:1	FEB 2018	Ha. Uttheemu/WS/02	0

TENDER PURPOSE