





Republic of Maldives

## **ADDENDUM 02**

### **Request for Proposals**

**For**

**Design, Build and Operation of 10MLD Sewage Treatment  
Plant in Hulhumalé Phase 1**

**Maldives Urban Development and Resilience Project**

**Credit No. / Grant No.: No-6537-MV/No-D554-MV  
RFP No: MV-MONPI-223416-CW-RFP**

**Issued on: 26<sup>th</sup> October, 2021**

**Issued by: National Tender  
Ministry of Finance  
Republic of Maldives**



1. Below changes are brought to the Data Sheet

ITP Clause	Tender data that supplements the ITT
<b>ITP 23.1</b>	<p>For <b><u>Proposal submission purposes</u></b> only, the Employer's address is: <b>For the attention:</b> <i>Ms. Fathimath Rishfa Ahmed</i> <b>Title/position:</b> <i>Chief Procurement Executive</i> <b>Address:</b> <i>National Tender,</i> <i>Ministry of Finance</i> <i>Ameenee Magu, Malé,</i> <i>Block 379, Postal Code 20379,</i> <i>Republic of Maldives</i> <b>Email address:</b> <a href="mailto:ibrahim.aflah@finance.gov.mv">ibrahim.aflah@finance.gov.mv</a></p>
	<p><b>CC:</b> <a href="mailto:tender@finance.gov.mv">tender@finance.gov.mv</a></p> <p><b>The deadline for Proposal submission is:</b> <b>Date:</b> 2<sup>nd</sup> November 2021 <b>Time:</b> 1300 hrs on Maldivian Time</p>
<b>ITP 26.1</b>	<p>The Proposal opening shall take place at: <i>National Tender,</i> <i>Ministry of Finance</i> <i>Ameenee Magu, Malé,</i> <i>Block 379, Postal Code 20379,</i> <i>Republic of Maldives</i></p> <p><b>Date:</b> 2<sup>nd</sup> November 2021 <b>Time:</b> 1300 hrs on Maldivian Time</p>



*[Handwritten signature]*

## 2. Following are the Changes to the bidding Document

- a) Added the following paragraph to Clause 1.2.3: Contractor is not required to make any adjustments to Pump Stations or Pumps. The existing outfalls can be tapped to divert the wastewater to STP for treatment. Once treated, the effluent from STP will need to be pumped back to the outfall pipe for discharging. Layout of these 2 pipes is shown in RFP document and attached herewith for easy reference. Each pipe is 400mm dia x 1500m long.
- b) Added sub-clause 3.11.4.1 C (f): Contractor shall use the British Standard (BS 8297) or equivalent to design prefabricated or precast elements.
- c) Additional clarification to Table 9.2 Construction Stage ESMP (Excavation and Dewatering/Ground Water): Dewatering should be done with URA (Utility Regulations Authority) and the charges imposed can be checked from their website, [www.ura.gov.mv](http://www.ura.gov.mv)
- d) Volume 2 RFP (Preliminary Drawings) No ductile Iron is used. It is a mistake. Pressure lines are HDPE lines and gravity flow lines are UPVC lines. Pipelines mentioned as Ductile iron to be read as HDPE Lines.
- e) Added the following paragraph to Clause 1.2.3: Road cutting and asphalt laying will not be required. The required piping work need to be done using underground service corridors. If required contractor is required to use horizontal drilling method for piping work.
- f) Volume 2 RFP (Preliminary Drawings) (Ref: TTI/MUD/MAL/PL/ESN/001B and layout TTI/MUD/MAL/GA/STP/001): The incoming pipe size modified to 400mm dia HDPE line.
- g) Added the following paragraph to Clause 3.11.4.1 (C) (a): Allowable bearing capacity is 150kPa and Ultimate bearing capacity is 210kPa. Minimum foundation depth is 1.2m below natural ground level
- h) Added the following paragraph to Clause 3.2.2: Pipe laying will be done through underground service corridors already provided in the roads. Where the service corridors are inadequate, contractor may use HDD (Horizontal Directional Drilling) to lay the pipes
- i) Added to 1st Paragraph of 1.3 Treatment process selection and design, of Part 2: Employers requirement: Bidders are required to treat the wastewater to the discharge standards given in the RFP document and where the RFP document contradicts with EPA / URA standards, EPA / URA standards shall prevail.
- j) Section III 2.2 (b) (ii) modified to be read as "For power costs, Amount of required electricity consumption for operation of the STP as specified in functional guarantee by proposer. Unit rate of 6.65 Maldivain Ruffiya per kWh (inclusive of Tax and any applicable duties) shall be included in the Proposed price and indicated separately from other cost. At the time of the Contract signing, the electrical cost for Operation Service will be recalculated based on prevailing Government rate during negotiation and amended in the Contract with new rate.
- k) Added the following line to 3.11.4.3, List of Reference: Bidder may use other relevant reference.



l) Section IV, Table C modified as follows;

m) Name of currency	n) Amounts payable
Local currency: _____	
Foreign currency #1: _____	
Foreign currency #2: _____	
Foreign currency #3: _____	
Provisional sums expressed in local currency _____	<i>[To be entered by the Bidder]</i>



*[Handwritten signature]*